DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WEATHERSFIELD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	8.360	A	R2-1	24	30		SPEED LIMIT 40 1310 1420 0840						1		X					CONTRACTOR WAS ALLOWED TO USE HORIZONTAL BRACKETS					# 1	PROVIDE A NEW SIGN FRAME TO HELP BRACE THE ASSEMBLY			
		A	R2-1	24	30			5.00								1		14.25' X								INSTALL IN SAME POSITION AS REMOVAL, NEXT TO "NO PARKING BEGINS" SIGNS	X		
		A	VR-644	24	12		BEGIN			1	1	1	1	~~X~~	X	1		14.75' X		POST WAS DAMAGED, SO IT WAS REPLACED. WERE SALVAGED AND RE-ERECTED PAY FOR REMOVALS.						REPLACED IN 2007			
		A	R8-3A	24	24		NO PARKING (SYMBOL)			1	1	1	1																
EB	8.402	A	W3-3	36	36								1		X														
		A	W3-3	36	36			9.00								2		14.25' 14.75' X								INSTALL BEHIND RAIL IN SAME POSITION AS REMOVAL	X		
EB	8.434	A	VD-062AS	72	16		BUSINESS DIRECTORY SIGN			1				X												YANKEE MOTEL <===			
		A	VD-062AS	72	16		BUSINESS DIRECTORY SIGN			1																CASA DEL SOL <===			
		A	VD-062AS	72	16		BUSINESS DIRECTORY SIGN			1																GETAWAY MTN. C.G. ===>			
EB	8.450	A	M2-1	21	15		JCT						1		X											(EXISTING SIGNS ON A SINGLE POST)			
		A	M1-4	24	24		US 5						1																
		A	M2-1	21	15		JCT						1																
		A	M1-5	24	24		VT 12						1																
		A	M2-1	21	15		(SEE NEXT PAGE)	2.19								2		16.5' 17.0' X							# 1A	BLACK ON WHITE	X		
		A	M1-4	24	24			4.00																		US-5			E-136B
SIGN SUMMARY SHEET							SHEET TOTALS	20.19	0.00	5	~~2~~ 0	~~2~~ 0	~~8~~ 6	0	0	5										~~91.5~~ ~~75~~			
								SF	SF	EA	EA	EA	EA	EA	EA	EA										FT			
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	778.3	0.0	47.0	9.0	9.0	180	0.0	0.0	108										1620.0			

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **WEATHERSFIELD EASTBOUND** PLOT DATE: **8/19/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
WEATHERSFIELD VT-131 EB 23 SHEET **144** OF **175**