DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WEATHERSFIELD WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	8.600	F	M1-5	30	24								1															
		F	M4-5	24	12								1															
		F	M1-1	24	24								1															
		F	M3-4	24	12			2.00								2		13.5' 14.0' X						# 1A	GREEN ON WHITE	X		
		F	M1-5	30	24			5.00																				E-136B
		F	M4-5	24	12			2.00																			WHITE ON BLUE	X		
		F	M1-1	24	24			4.00																				X		
WB	8.539	F	D2-1	72	12		CAVENDISH 15			1				X													AS-NEW. BOTH SIGNS REPLACED IN 2007, RETAIN ALL			
		F	D2-1	72	12		LUDLOW 24			1																				
WB	8.508	F	R2-1	24	30								1		X															
		F	VR-644	24	12								1		X												(TWO POSTS TO REMOVE)			
		F	R8-3A	24	24								1																	
		F	R2-1	24	30			5.00								2		15.25' 15.75' X			USED A HORIZON-TAL BRACE.		# 1	~~USE A SIGN FRAME TO~~ BRACE THE TWO ~~ASSEMBLIES~~; INSTALL AS SHOWN POST.	X		
		F	VR-644P	24	12			2.00																			INSTALL PLAQUE ON TOP; **BLACK ON WHITE** (2009 MUTCD SIGN CODE, BUT USE THE DETAIL)		6	
		F	R8-3A	24	24			4.00																				X		
							SHEET TOTALS	24.00	0.00	2	0	0	6	0	0	4			~~58.5~~ ~~60~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
							TOWN DIRECTIONAL TOTALS	644.2	0.0	17.0	1.0	1.0	153	0.0	0.0	78			1170.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **WEATHERSFIELD WESTBOUND** PLOT DATE: **8/19/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
WEATHERSFIELD VT-131 WB 3 SHEET **153** OF **175**