| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **SHAFTSBURY VT-7A** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| | | A | M6-3S | 21 | 15 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-4 | 24 | 12 | | | 2.00 | | | | | | | | 2 | | 14.5<br>15.75<br>X | | | | | | | #2 | GREEN ON WHITE ROUTE MARKERS | | 7 | E-136B |
| | | A | M1-5 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | M6-1 | 21 | 15 | | | 2.19 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | M3-1 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | VM-078 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | M1-5 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | M6-3 | 21 | 15 | | | 2.19 | | | | | | | | | | | | | | | | | | | | E-136B |
| NB | 1.206 | A | R2-1 | 24 | 30 | | SPEED LIMIT 35 | | | | | | 1 | | X | | | | | | | | | | | | | |
| NB | 1.225 | A | D2-1 | 72 | 10 | | | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | A | D2-1 | 72 | 10 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-1S | 24 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | VM-078S | 24 | 12 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M1-5 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | D2-1 | 72 | 12 | | | 6.00 | | | | | | | | 2 | | 16.0<br>17.0<br>X | | | | | | | | 5 | | |
| | | | | | | | SHEET TOTALS | 24.38 | 0.00 | 0 | 0 | 0 | 7 | 0 | 0 | 4 | | ~~60~~ 63.25 | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 269.1 | 0.0 | 15.0 | 5.0 | 5.0 | 62 | 0.0 | 0.0 | 44 | | 660.0 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **SHAFTSBURY NB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
SHAFTSBURY NORTHBOUND SHEET 4 SHEET **11** OF **90**