DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SHAFTSBURY VT-7A							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	3.440	A	W2-1M	30	30		MODIFIED CROSSROAD					1				1		14.75 X								RELOCATE SIGN ASSEMBLY 250 FEET NORTH.			
NB	3.530	C	VR-017	24	30								1		X												TUNIC RD. (TH-56)			
		C	VR-017	24	30			5.00								1		13.25 X										4	
NB	3.534	D	R1-1	30	30								1		X												TUNIC RD. (TH-56)			
		D	R1-1	30	30			6.25								1		13.25 X									X		
NB	4.101	A	W11-7	30	30		EQUESTRIAN						1		X														
NB	4.604	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
NB	4.733	A	VD-062AL	72	16		BUSINESS SIGN			1				X															
		A	VD-062B	72	16		BUSINESS SIGN			1																			
NB	5.004	A	W1-2L	30	30		LEFT CURVE						1		X														
		A	W13-1	18	18		40 MPH ADVISORY						1																
NB	5.019	C	VR-017	24	30								1		X												HIDDEN VALLEY RD. (TH-67)			
		C	VR-017	24	30			5.00								1		13.25 X										4	
NB	5.026	D	R1-1	30	30								1		X												HIDDEN VALLEY RD. (TH-67)			
		D	R1-1	30	30			6.25								1		13.25 X									X		
							SHEET TOTALS	22.50	0.00	2	0	1	8	0	0	5		~~75~~ 67.75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	269.1	0.0	15.0	5.0	5.0	62	0.0	0.0	44		660.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: SHAFTSBURY NB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
SHAFTSBURY NORTHBOUND SHEET 7

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 14 OF 90