DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SHAFTSBURY VT-7A							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.146	A	W1-2L	30	30			6.25								1		15.5 X								INSTALL AT SOUTH END OF GUARDRAIL SECTION. SOUTH OF POLE #173T/280/67/105.	X		
		A	W13-1	18	18			2.25																			X		
NB	5.186	A	W1-8	18	24		CHEVRON						1		X											REINSTALL BR-7 PLAQUE. REMOVE AND DISCARD 5.20 MM.			
		A	N/A				BRIDGE 7 PLAQUE				1	1	1																
		A	W2-2RM	30	30			6.25								1		14.0 X										6	
NB	5.235	A	W1-8	18	24		CHEVRON						1		X														
NB	5.256	A	W1-8	18	24		CHEVRON						1		X														
		A	W11-8	30	30			6.25								1		15.0 X									INSTALL 475 FEET IN ADVANCE OF OLD DEPOT RD.	X		
NB	5.306	A	W1-8	18	24		CHEVRON						1		X														
NB	5.311	A	VR-928R	30	30								1		X														
		A	VR-928R	30	30			6.25								1		14.75 X											E-145A
NB	5.336	C	VR-017	24	30								1		X												OLD DEPOT RD. (TH-1)			
		C	N/A	18	24		TOWN' SPEED ZONE AHEAD						1																
		C	VR-017	24	30			5.00								1		13.5 X										4	
NB	5.345	D	R1-1	30	30								1		X												OLD DEPOT RD. (TH-1)			
							SHEET TOTALS	32.25	0.00	0	1	1	~~9~~ 8	0	0	5		~~75~~ 72.75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	269.1	0.0	15.0	5.0	5.0	62	0.0	0.0	44		660.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **SHAFTSBURY NB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
SHAFTSBURY NORTHBOUND SHEET 8 SHEET **15** OF **90**