DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	TUBULAR STEEL Ø (IN) (LB / FT) FOUNDATION	3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
SHAFTSBURY VT-7A							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.637	A	W11-2	30	30	FYG	PEDESTRIAN			1				X															
		A	W16-4	30	24	FYG	NEXT 1000 FEET			1																			
							SHEET TOTALS	0.00	0.00	2	0	0	0	0	0	0			0										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
							TOWN DIRECTIONAL TOTALS	269.1	0.0	15.0	7.0 ~~5.0~~	7.0 ~~5.0~~	69 ~~62~~	0.0	0.0	44			618.00 ~~660.0~~										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **SHAFTSBURY NB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
SHAFTSBURY NORTHBOUND SHEET 10 SHEET **17** OF **90**