DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SHAFTSBURY VT-7A							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W13-1	18	18			2.25																			X		
SB	5.282	F	VD-062AL	72	16		BUSINESS SIGN			1																			
		F	VD-062B	72	16		BUSINESS SIGN			1																			
SB	5.220	G	VR-017	24	30								1		X												BIRCH HILL RD. (TH-96)			
		G	VR-017	24	30			5.00								1		12.5 X										4	
SB	5.214	H	R1-1	30	30								1		X												BIRCH HILL RD. (TH-96)			
		H	R1-1	30	30			6.25								1		13.25 X									X		
SB	4.870	F	OM-3R	12	36		DELINEATOR REMOVED	3.00					1			1		11.0 X								INSTALL AT 4 FT AND IN PLACE OF DELINEATOR POST AT NORTH END OF CURBING	X		
SB	4.477	G	VR-017	24	30								1		X												HIGHLAND WOODS DR (TH-99)			
		G	VR-017	24	30			5.00								1		13.25 X										4	
SB	4.471	H	R1-1	30	30								1		X												HIGHLAND WOODS DR (TH-99)			
		H	R1-1	30	30			6.25								1		14.25 X									X		
SB	4.329	F	OM-3R	12	36		DELINEATOR REMOVED	3.00					1			1		11.0 X								INSTALL AT 4 FT AND IN PLACE OF DELINEATOR POST AT GOVERNORS ROCK MOTEL	X		
SB	3.854	F	VW-059	30	30		HIDDEN DRIVE						1		X															
SB	3.741	F	R2-1	24	30								1		X															
SIGN SUMMARY SHEET							SHEET TOTALS	30.75	0.00	2	0	0	~~8~~ 6	0	0	6			~~90~~ 75.25										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	217.7	0.0	26.0	5.0	5.0	46	0.0	0.0	38			570.0										

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **SHAFTSBURY SB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
SHAFTSBURY SOUTHBOUND SHEET 2 SHEET **19** OF **90**