DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SHAFTSBURY VT-7A							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	R2-1	24	30			5.00								1		13.25 X									X		
SB	3.619	F	W2-1M	30	30		MODIFIED CROSSROAD			1				X															
SB	3.502	G	VR-017	24	30								1		X											W. MOUNTAIN RD. (TH-54)			
		G	VR-017	24	30			5.00								1		14.0 X										4	
SB	3.494	H	R1-1	30	30								1		X															
		H	R1-1	30	30			6.25								1		13.25 X									W. MOUNTAIN RD. (TH-54)	X	
SB	2.944	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
		F	VD-062B	72	16		BUSINESS SIGN			1																			
SB	2.672	F	W2-2MR	30	30		RIGHT SIDE ROAD (UP 45 DEG)			1				X															
		F	W16-8	20	8		MYERS RD			1																			
SB	2.589	G	VR-017	24	30								1		X											MYERS RD (TH-7)			
		G	VR-017	24	30			5.00								1		13.5 X										4	
SB	2.587	H	R1-1	30	30								1		X											MYERS RD (TH-7)			
		H	R1-1	30	30			6.25								1		15.25 X										X	
SB	1.800	F	W3-5	36	36		SPEED REDUCTION (40)			1				X															
							SHEET TOTALS	27.50	0.00	6	0	0	4	0	0	5		~~75~~ 69.25											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	217.7	0.0	26.0	5.0	5.0	46	0.0	0.0	38		570.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **SHAFTSBURY SB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
SHAFTSBURY SOUTHBOUND SHEET 3 SHEET **20** OF **90**