DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
		A	R2-1	24	30			5.00								1		13.25 X									X		
NB	0.397	A	R2-1	24	30		SPEED LIMIT 30						1		X														
		A	M3-1	24	12			2.00								1		14.0 X								GREEN ON WHITE ROUTE MARKERS.			
		A	M1-5	24	24			4.00																					E-136B
NB	0.463	A	VD-062AS	72	16		BUSINESS SIGN			1				X															
NB	0.509	A	R2-1	24	30								1		X															
		A	R2-1	24	30			5.00								1		13.25 X									X		
NB	0.516	C	VR-017	24	30								1	X													RIVER RD. (TH-13)			
		C	VR-017	24	30			5.00																			REPLACE SIGN AND RETAIN SIGN POST.		4	
NB	0.522	D	R1-1	30	30								1	X													RIVER RD. (TH-13)			
		D	R1-1	30	30			6.25																			REPLACE SIGN AND RETAIN SIGN POST.	X		
NB	0.610	C	VR-017	24	30								1	X													WINHALL HOLLOW RD. (TH-2)			
		C	VR-017	24	30			5.00																					4	
		C	N/A				TOWN'S BUCKLE-UP SIGN						1														REMOVE BUCKLE-UP SIGN AND RETURN TO TOWN.			
NB	0.617	D	R1-1	30	30								1	X													WINHALL HOLLOW RD. (TH-2)			
							SHEET TOTALS	32.25	0.00	1	0	0	7	0	0	3		-45- 40.5											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	456.7	0.0	5.0	3.0	3.0	79	0.0	0.0	51		765.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **WINHALL NB.XLS**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WINHALL NORTHBOUND SHEET 3

PLOT DATE: **8/26/2010**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **29** OF **90**