DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	2.343	D	R1-1	30	30								1	X													STONEY HILL RD. (TH-12)			
		D	R1-1	30	30			6.25																			REPLACE SIGN AND RETAIN SIGN POST.	X		
NB	2.710	C	VR-017	24	30								1	X													LOWER STRATTON VALLEY RD. (TH-29)			
		C	VR-017	24	30			5.00																			REPLACE SIGN AND RETAIN SIGN POST.		4	
		C	N/A				TOWN'S NO PARKING SIGN				~~1~~	~~1~~															INSTALL BELOW NEW LL24 K SIGN.			
NB	2.717	D	R1-1	30	30								1		X												LOWER STRATTON VALLEY RD. (TH-29)			
		D	R1-1	30	30			6.25								1		15.5 X									X		
NB	3.158	A	W1-5R	30	30			6.25								1		15.5 X								INSTALL 200 FEET SOUTH OF EXISTING WINDING ROAD SIGN.	X		
		A		24	18			3.00																						
NB	3.196	A	W1-5L	30	30		LEFT WINDING ROAD						1	X																
		A	W1-2R	30	30			6.25																			INSTALL NEW SIGN ON EXISTING POST.	X		
NB	3.256	A	VW-060	30	30		HIDDEN DRIVES						1		X															
		A	VW-054R	30	30			6.25								1		15.25 X										6	
NB	4.000	A	W1-2L	30	30								1	X																
		A	W1-2L	30	30			6.25																			REPLACE SIGN AND RETAIN SIGN POST.	X		
							SHEET TOTALS	~~45.50~~ ~~42.50~~	0.00	0	~~1~~	~~1~~	6	0	0	3		~~45~~ 46.25										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	456.7	0.0	5.0	~~2.0~~ ~~3.0~~	~~2.0~~ ~~3.0~~	79	0.0	0.0	51		765.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: WINHALL NB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
WINHALL NORTHBOUND SHEET 6

PLOT DATE: 8/26/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 32 OF 90