DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	• REF SHEET 38 OF 90 FOR UPDATE SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.404	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1	X												OLD ROUTE 30. (TH-23)			
		C	VR-017	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.		4	
NB	5.411	D	R1-1	30	30		STOP						1		X											OLD ROUTE 30. (TH-23)			
		D	R1-1	30	30			6.25								1		13.25 X									X		
NB	5.685	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X											OLD ROUTE 30. (TH-23)			
		C	VR-017	24	30			5.00								1		13.25 X										4	
NB	5.702	D	R1-1	30	30		STOP						1		X											OLD ROUTE 30. (TH-23)			
		D	R1-1	30	30			6.25								1		13.25 X											
NB	5.790	A	S3-1	30	30		* SCHOOL BUS STOP AHEAD						1		X														
NB	5.800	A	S3-1	36	36	FYG	SCHOOL BUS STOP AHEAD	9.00								~~1~~ 2		14.5 15.0 X								INSTALL 50 FEET NORTH OF EXISTING. PLACED ON 2 POSTS	X		
NB	5.840	A	W2-2R	30	30								1		X														
		A	W2-2RM	30	30			6.25								1		14.0 X										6	
NB	5.907	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1	X												FRENCH HOLLOW RD. (TH-6)			
		C	VR-017	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.		4	
NB	5.921	D	R1-1	30	30		STOP						1	X												FRENCH HOLLOW RD. (TH-6)			
							SHEET TOTALS	42.75 SF	0.00 SF	0 EA	0 EA	0 EA	8 EA	0 EA	0 EA	~~5~~ 6 EA		~~75~~ 83.25 FT										
							TOWN DIRECTIONAL TOTALS	456.7	0.0	5.0	3.0	3.0	79	0.0	0.0	51		765.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: WINHALL NB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
WINHALL NORTHBOUND SHEET 8

PLOT DATE: 8/26/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE