DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		H	R1-1	30	30			6.25								1		13.25 X									X		
SB	6.932	F	W1-6	48	24			8.00								2		12.75 12.75 X								INSTALL 25 FEET SOUTH OF STOP SIGN.	X		
SB	6.930	F	W1-8	18	24		CHEVRON						1		X														
		E	W1-8	18	24		CHEVRON						1																
SB	6.907	F	W1-8	18	24		CHEVRON						1		X														
SB	6.857	G	VR-017	24	30								1		X															
		G	VR-017	24	30			5.00								1		13.25 X								WINHALL WOOD RD. (TH-30)		4	
SB	6.786	H	R1-1	30	30								1		X															
		H	R1-1	30	30			6.25								1		13.75 X								WINHALL WOOD RD. (TH-30)	X		
SB	6.800	F	VW-000	30	30		MOOSE CROSSING						1		X														
		F	W7-3A	24	18		NEXT 5 MILES						1																
SB	6.772	F	VW-000	30	30			6.25								1		15.0 X								INSTALL ASSEMBLY 150 FEET SOUTH OF CURRENT LOCATION - NORTH SIDE OF BR #48.		6	
		F	W7-3A	24	18			3.00																			X		
SB	6.640	G	VR-017	24	30								1		X												SIGNAL HILL RD. (TH-40)			
		G	VR-017	24	30			5.00								1		13.25 X										4	
							SHEET TOTALS	39.75	0.00	0	0	0	8	0	0	7		~~105~~ 94											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	457.6	0.0	6.0	0.0	0.0	81	0.0	0.0	65		975.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **WINHALL SB.XLS**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
WINHALL SOUTHBOUND SHEET 4

PLOT DATE: **7/13/2010**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **42** OF **90**