DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	5.051	H	R1-1	30	30								1		X											CAPEN RD. (TH-24)			
		H	R1-1	30	30			6.25								1		13.25 X								X		
SB	4.769	G	VR-017	24	30								1	X												CAPEN RD. (TH-24)			
		G	VR-017	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.		4	
SB	4.758	H	R1-1	30	30								1		X															
		H	R1-1	30	30			6.25								1		13.25 X								CAPEN RD. (TH-24)	X		
SB	4.353	F	W1-2R	30	30		RIGHT CURVE						1		X															
SB	4.282	F	W1-2R	30	30			6.25								1		14.0 X								INSTALL 375 FEET SOUTH OF EXISTING SIGN AND ACROSS FROM BEAVER ST. (TH-55).	X		
SB	4.007	F	W7-1B	30	30								1	X																
		F	W7-1B	30	30			6.25																		REPLACE SIGN AND RETAIN SIGN POST.	X		
		F	W7-3A	24	18			3.00																					
SB	3.955	F	W1-5L	30	30								1	X																
		F	W1-5L	30	30			6.25																		REPLACE SIGN AND RETAIN SIGN POST.	X		
		F	W7-3A	24	18			3.00																					
SB	3.905	F	W1-2L	30	30			6.25								1		14.0 X								INSTALL BEHIND NORTH END OF RAIL AND SOUTH OF COREY RD.	X		
							SHEET TOTALS	48.50	0.00	0	0	0	6	0	0	4		~~60~~ 54.5									
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT									
							TOWN DIRECTIONAL TOTALS	457.6	0.0	6.0	0.0	0.0	81	0.0	0.0	65		975.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **WINHALL SB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
WINHALL SOUTHBOUND SHEET 6 SHEET **44** OF **90**