DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
SB	0.521	F	R2-1	24	30								1	X														
		F	R2-1	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.	X		
SB	0.480	F	S3-4A	30	30		SCHOOL BUS TURN AROUND			1				X														
SB	0.445	F	W11-2YG	30	30								1		X													
		F	W16-7FYG	24	12								1															
		E	W11-2YG	30	30								1															
		E	W16-7FYG	24	12								1															
		F	W11-2	30	30	FYG		6.25								1		15.0 X							INSTALL SIGNS BACK TO BACK AS EXISTING.	X		
		F	W16-7pL	24	12	FYG		2.00																		X		
		E	W11-2	30	30	FYG		6.25																		X		
		E	W16-7pR	24	12	FYG		2.00																		X		
SB	0.390	F	D1-1S	72	10								1		X													
		F	D1-1S	72	12			6.00								2		12.0 12.25 X									5	
SB	0.373	G	VR-017	24	30								1	X												STRATTON MTN ACCESS RD. (TH-1)			
		G	VR-017	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.		4	
							SHEET TOTALS	32.50	0.00	1	0	0	7	0	0	3		~~45~~ 39.25									
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT									
							TOWN DIRECTIONAL TOTALS	457.6	0.0	6.0	0.0	0.0	81	0.0	0.0	65		975.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: WINHALL SB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
WINHALL SOUTHBOUND SHEET 10

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 48 OF 90