DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WINHALL VT-30							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	0.130	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								1		13.75 X									X		
SB	0.065	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
SB	4.140	F	VW-054R	30	30			6.25								1		14.5 X								SIGN AFTER PROJECT LET			
SIGN SUMMARY SHEET							SHEET TOTALS	11.25 ~~5.00~~	0.00	1	0	0	1	0	0	2 ~~1~~		~~15~~ 28.25											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	463.85 ~~457.6~~	0.0	6.0	0.0	0.0	82 ~~81~~	0.0	0.0	66 ~~65~~		923.25 ~~975.0~~											

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **WINHALL SB.XLS** | PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** | DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** | CHECKED BY: **A. GAMBLE**
WINHALL SOUTHBOUND SHEET 12 | SHEET **50** OF **90**