DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
DORSET US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN				I	I	I			I		13.25 X								"SHS"-STANDARD HIGHWAY SIGNS			
NB	5.148	A	VR-921L	30	30								1		X												• SIGN WAS INSTALLED THEN MOVED FURTHER OFF ROAD			
		A	VR-921L	30	30			6.25								1		13.25 X											E-145A
NB	5.243	A	M3-1	24	12								1	X															
		A	M1-4	24	24								1																
		A	M3-1	24	12			2.00																		REPLACE BLACK ON WHITE ROUTE MARKERS AND RETAIN SIGN POST.	X		
		A	M1-4	24	24			4.00																			X		
NB	5.520	A	R2-1	24	30								1		X															
NB	5.530	A	R2-1	24	30			5.00								1		14.0 X								INSTALL 50 FEET NORTH OF EXISTING SL50 SIGN ASSEMBLY.	X		
NB	6.615	A	R2-1	24	30								1		X															
		A	R2-1	24	30			5.00								1		13.25 X									X		
NB	6.646	A	M3-1	24	12		NORTH						1		X														
		A	M1-4	24	24		US-7						1																
NB	6.656	A	M3-1	24	12			2.00								1		15.0 X								INSTALL 50 FEET NORTH OF EXISTING ROUTE MARKER ASSEMBLY	X		
		A	M1-4	24	24			4.00																			X		
							SHEET TOTALS	28.25	0.00	0	~~0~~ 1	~~0~~ 1	~~7~~ 8	0	0	~~4~~ 5		~~60~~ 68.75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	163.8	0.0	1.0	~~1.0~~ 2.0	~~1.0~~ 2.0	~~32~~ 34	0.0	0.0	24		~~360.0~~ 331.75											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: DORSET NB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
DORSET NORTHBOUND SHEET 5

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 55 OF 90