DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
DORSET US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	6.690	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS						1		X													
SB	6.578	F	R2-1	24	30								1	X														
		F	R2-1	24	30			5.00																		REPLACE SIGN AND RETAIN SIGN POST.	X		
SB	6.545	F	M3-3	24	12								1	X														
		F	M1-4	24	24								1															
		F	M3-3	24	12			2.00																	REPLACE BLACK ON WHITE ROUTE MARKERS AND RETAIN SIGN POST.	X		
		F	M1-4	24	24			4.00																			X		
SB	5.589	F	VD-018	30	18								1	X														
		F	VD-018	30	18			3.75																		REPLACE SIGN AND RETAIN SIGN POST.		5	
SB	5.530	F	R2-1	30	36			7.50								1		15.0 X								INSTALL 50 FEET NORTH OF EXISTING AND ACROSS FROM NEW NB SL50.		4	
SB	5.520	F	R2-1	24	30		SPEED LIMIT 45						1		X													
SB	5.367	F	W2-2MR	30	30								1	X														
		F	W2-2MR	30	30			6.25																		REPLACE SIGN AND RETAIN SIGN POST.		6	
SB	5.319	F	R2-1	24	30		SPEED LIMIT 45			1				X														
SB	5.270	F	VR-921R	30	30								1	X														
							SHEET TOTALS	28.50	0.00	1	0	0	8	0	0	1		15										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	206.7	0.0	5.0	1.0	1.0	47	0.0	0.0	21		315.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **DORSET SB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
DORSET SOUTHBOUND SHEET 1 SHEET **56** OF **90**