DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
DORSET US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	2.175	F	W11-2	30	30	FYG		6.25								1		15.5 X								INSTALL IN-LINE WITH MARBLEDGE MOTEL SIGN.	X		
		F	W16-9P	24	12	FYG		2.00																			X		
SB	2.116	F	R8-3A	24	24								1																
		F	VR-644P	24	12								1		X														
		F	VR-644P	24	12			2.00								1		14.25 X								BLACK ON WHITE		4	
		F	R8-3	24	24			4.00																			X		
SB	2.111	G	VR-017	24	30								1														SQUIRREL HOLLOW RD. (TH-22)			
		H	R1-1	30	30								1																
			N/A				TOWN'S STREET NAME SIGN				1	1	1														REINSTALL TOWN'S STREET NAME SIGN ON TOP OF POST.			
		G	VR-017	24	30			5.00								1		13.75 X								INSTALL BACK-TO-BACK AS EXISTING.		4	
		H	R1-1	30	30			6.25																			X		
SB	2.104	H	R1-1	30	30								1														SQUIRREL HOLLOW RD. (TH-22)			
		H	R1-1	30	30			6.25								1		13.25 X									X		
SB	2.051	F	R8-3A	24	24								1																
		F	M4-6P	24	12								1		X														
							SHEET TOTALS	31.75	0.00	0	1	1	~~8~~ 7	0	0	4			~~60~~ 56.75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
							TOWN DIRECTIONAL TOTALS	206.7	0.0	5.0	1.0	1.0	47	0.0	0.0	21			315.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **DORSET SB.XLS**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **J. KELLY**
DORSET SOUTHBOUND SHEET 5

PLOT DATE: **7/13/2010**
DRAWN BY: **J. KELLY**
CHECKED BY: **A. GAMBLE**
SHEET **60** OF **90**