DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MOUNT TABOR US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.000	C	VD-024	60	7.5								1		X														
		C	VD-025	60	7.5								1																
		C	VD-024	72	10		Mt. Tabor / Dorset	5.00								2		13.5 13.5 X										4	
		C	VD-025	72	10		Rutland Co. / Bennington Co.	5.00																				4	
		C	VD-700	6	10		0070 1113 0000 / 0070 0203 0672	0.42					1														INSTALL ON LH POST BELOW MT. TABOR.			E-138
		C	VD-700	6	10			0.42					1														INSTALL ON RH POST BELOW DORSET.			E-138
NB	0.103	C	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS						1		X														
NB	0.691	A	W10-2R	36	36		CROSSROAD W/TRACKS ON RIGHT			1				X															
NB	0.747	A	VD-062B	72	16		BUSINESS SIGN			1				X															
NB	0.830	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X												SOUTH END RD. (TH-5)			
		C	VR-017	24	30			5.00								1		13.75 X									EAST OF RR TRACKS.		4	
NB	0.834	D	R1-1	30	30		STOP						1		X												SOUTH END RD. (TH-5)			
		D	R1-1	30	30			6.25								1		14.75 X										X	
NB	1.359	A	W10-3R	36	36		RIGHT SIDE ROAD W/TRACKS			1				X															
NB	1.523	C	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	22.09	0.00	3	0	0	~~8~~ 6	0	0	4		~~60~~ 55.5										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	134.1	0.0	7.0	2.0	2.0	29	0.0	0.0	18		270.0										

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: MOUNT TABOR NB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
MOUNT TABOR NORTHBOUND SHEET 1

PLOT DATE: 8/26/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 63 OF 90