DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MOUNT TABOR US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.579	A	M3-1	24	12								1	X															
		A	M1-4	24	24								1																
		A	M3-1	24	12			2.00																		INSTALL NEW BLACK ON WHITE ROUTE MARKERS AND RETAIN SIGN POST.	X		
		A	M1-4	24	24			4.00																				X		
NB	1.627	A	R2-1	24	30								1	X																
		A	R2-1	24	30			5.00																			REPLACE SIGN AND RETAIN SIGN POST.	X		
NB	1.838	A	W2-2ML	30	30		LEFT SIDE ROAD W/SMALL SIDE						1		X														
	1.915	A	W2-2ML	30	30			6.25								1		15.0 X								INSTALL 300 FEET SOUTH OF GRIFFITH HILL RD(TH-7).		6	
NB	2.021	A	M3-1	24	12		NORTH						1		X														
		A	M1-4	24	24		US 7						1																
NB	2.062	A	R2-1	24	30		SPEED LIMIT 50						1		X														
NB	2.440	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
NB	2.478	A	VD-062B	72	16		BUSINESS SIGN			1				X															
NB	2.525	A	VD-062B	72	16		BUSINESS SIGN			1				X															
NB	2.572	A	VD-062AS	72	16		BUSINESS SIGN			1				X															
							SHEET TOTALS	17.25	0.00	3	0	0	8	0	0	1		15											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	134.1	0.0	7.0	2.0	2.0	29	0.0	0.0	18		270.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **MOUNT TABOR NB.XLS** PLOT DATE: **8/26/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
MOUNT TABOR NORTHBOUND SHEET 2 SHEET **64** OF **90**