DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MOUNT TABOR US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	3.360	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X														
SB	3.310	F	VD-062AS	72	16		BUSINESS SIGN			1				X															
		F	VD-062AS	72	16		BUSINESS SIGN			1																			
SB	3.270	F	VD-062B	72	16		BUSINESS SIGN			1				X															
SB	3.230	F	VD-062B	72	16		BUSINESS SIGN			1				X															
* SB	3.180	F	R2-1	30	36		SPEED LIMIT 45	7.50								1		15.5 X									INSTALL 60 FEET NORTH OF EXISTING AND DIRECTLY ACROSS FROM NB SL-50. *		4	
SB	3.163	F	R2-1	24	30		SPEED LIMIT 45						1		X												REFER TO SHEET 67 OF 90			
SB	3.105	F	W11-2	30	30								1																
		F	VW-113	24	18		HANDICAPPED PERSON AHEAD						1																
		F	W11-2	30	30	FYG	HANDICAPPED PERSON AHEAD	6.25								1		15.0 X										X		
		F	W16-9P	24	12	FYG	HANDICAPPED PERSON AHEAD	2.00																				X		
SB	3.057	F	W2-1M	48	48								1		X														
		F	W13-1	24	24								1																
		F	W2-1M	48	48		40 M.P.H.	16.00								2		17.0 17.25 X										6	
		F	W13-1	24	24		40 M.P.H.	4.00																				X		
							SHEET TOTALS	35.75	0.00	4	0	0	6	0	0	4		~~60~~ 64.75												
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT												
							TOWN DIRECTIONAL TOTALS	173.3	0.0	7.0	2.0	2.0	32	0.0	0.0	17		255.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **MOUNT TABOR SB.XLS** PLOT DATE: **8/26/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
MOUNT TABOR SOUTHBOUND SHEET 1 SHEET **68** OF **90**