DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MOUNT TABOR US-7							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHS"-STANDARD HIGHWAY SIGNS			
SB	2.733	F	M3-3	24	12								1		X														
		F	M1-4	24	24								1																
		F	M3-3	24	12			2.00								1		15.5 X								BLACK ON WHITE ROUTE MARKERS.	X		
		F	M1-4	24	24			4.00																				X		
SB	2.620	F	R2-1	24	30			5.00								1		15.0 X								INSTALL 60 FEET NORTH OF EXISTING AND DIRECTLY ACROSS FROM THE NEW NB SL-45 SIGN ASSEMBLY.	X		
		E	R2-1	30	36			7.50																					4	
SB	2.609	F	R2-1	24	30								1		X												REMOVE 2.60 MM SIGN.			
SB	2.102	F	W2-2RM	30	30		RIGHT SIDE ROAD W/SMALL SIDE						1		X															
	2.032	F	W2-2RM	30	30			6.25								1		15.5 X								INSTALL 300 FEET NORTH OF GRIFFITH HILL RD. (TH-7).		6	
SB	1.977	G	VR-017	24	30			5.00								1		14.75 X								GRIFFITH HILL RD. (TH-7)		4	
SB	1.966	H	R1-1	30	30								1		X												GRIFFITH HILL RD. (TH-7)			
		H	R1-1	30	30			6.25								1		14.0 X									X		
			N/A				TOWN'S STREET NAME SIGN				1	1	1														REINSTALL TOWN'S STREET NAME SIGN ON TOP OF NEW POST.			
SB	1.850	G	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS						1		X															
SB	1.642	F	W10-3L	36	36		LEFT SIDE ROAD W/TRACKS			1				X																
							SHEET TOTALS	36.00	0.00	1	1	1	~~7~~ 6	0	0	5		~~75~~ 74.75											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	173.3	0.0	7.0	2.0	2.0	32	0.0	0.0	17		255.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **MOUNT TABOR SB.XLS** PLOT DATE: **8/26/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
MOUNT TABOR SOUTHBOUND SHEET 3 SHEET **70** OF **90**