| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB/FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB/FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB/FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **MOUNT TABOR US-7** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| SB | 0.826 | H | R1-1 | 30 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | SOUTH END RD. EXT. (TH-9) | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | | | REPLACE SIGN AND RETAIN SIGN POST. TRIM BRUSH. | X | | |
| SB | 0.719 | G | VR-017 | 24 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | TROLL HILL RD. (TH-8) | | | |
| | | G | VR-017 | 24 | 30 | | | 5.00 | | | | | | | | 1 | | 15.5<br>X | | | | | | | | | | | 4 | |
| | | G | N/A | 18 | 24 | | TOWN'S SPEED LIMIT 30 SIGN | | | | 1 | 1 | 1 | | | | | | | | | | | | | | REINSTALL TOWN'S SPEED LIMIT 30 SIGN BELOW NEW LL24K SIGN. | | | |
| SB | 0.713 | H | R1-1 | 30 | 30 | | | | | | | | 1 | | X | | | | | | | | | | | | TROLL HILL RD. (TH-8) | | | |
| | | H | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | 13.5<br>X | | | | | | | | | | X | |
| SB | 0.677 | F | M3-3 | 24 | 12 | | | | | | | | 1 | X | | | | | | | | | | | | | | | |
| | | F | M1-4 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | | |
| | | F | M3-3 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | REPLACE BLACK ON WHITE ROUTE MARKERS AND RETAIN SIGN POST. | X | | |
| | | F | M1-4 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | | X | |
| SB | 0.633 | F | R2-1 | 24 | 30 | | | | | | | | 1 | X | | | | | | | | | | | | | | | | |
| | | F | R2-1 | 24 | 30 | | | 5.00 | | | | | | | | | | | | | | | | | | | REPLACE SIGN AND RETAIN SIGN POST. | X | | |
| SB | 3.025 | F | DI-1 | 72 | 12 | | DANBY ⟶ | 6.00 | | | | | 1 | | | | | | | | | | | | | | | | |
| SB | 1.224 | G | VR-017 | 24 | 30 | | LLL | — | | | 1 | 1 | 1 | | | 1 | | 14.25<br>X | | | | | | | | | SIGN WAS INSTALLED ON 7-20-11 BUT POST WAS DAMAGED. | | | |
| | | | | | | | SHEET TOTALS | ~~34.50~~ 28.50 SF | 0.00 SF | 0 EA | ~~2~~ 1 EA | ~~2~~ 1 EA | ~~9~~ 6 EA | 0 EA | 0 EA | ~~3~~ 2 EA | | ~~30~~ 43.25 FT | | | | | | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | ~~179.25~~ 173.3 | 0.0 | 7.0 | ~~5.0~~ 2.0 | ~~5.0~~ 2.0 | ~~38~~ 32 | 0.0 | 0.0 | ~~19~~ 17 | | ~~274.0~~ 255.0 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **MOUNT TABOR SB.XLS** PLOT DATE: **8/26/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
MOUNT TABOR SOUTHBOUND SHEET 5 SHEET **72** OF **90**