DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOCKBRIDGE VT-107							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	0.400	A	VW-054R	30	30								1		X														
		A	VW-054R	30	30			6.25								1		14.0 X										6	
EB	0.682	A	W1-5R	30	30								1		X														
EB	0.864	A	W8-5	30	30								1	X															
		A	W7-3A	24	18								1																
		A	W8-5	30	30			6.25																	REPLACE SIGNS AND RETAIN SIGN POSTS.	X		
		A	W7-3A	24	18			3.00																			X		
EB	0.944	A	W1-2R	30	30			6.25								1		15.0 X									INSTALL 425 FEET EAST OF PREVIOUS ASSEMBLY.	X		
EB	2.335	A	W1-2L	30	30		LEFT CURVE						1		X														
		A	W13-1	18	18		40 MPH ADVISORY						1																
EB	2.434	A	W1-2L	30	30			6.25								1		15.5 X									INSTALL 550 FEET EAST OF EXISTING LEFT CURVE ASSEMBLY.	X		
		A	W13-1	18	18			2.25																			X		
EB	2.530	C	VR-017	24	30								1		X													RANNY RD. (TH-18)			
		C	VR-017	24	30			5.00								1		13.25 X										4	
EB	2.540	D	R1-1	30	30								1		X												RANNY RD. (TH-18)			
							SHEET TOTALS	35.25 SF	0.00 SF	0 EA	0 EA	0 EA	8 EA	0 EA	0 EA	4 EA		~~60~~ 57.75 FT											
							TOWN DIRECTIONAL TOTALS	131.8	0.0	24.0	1.0	1.0	23	0.0	0.0	19		285.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE - SOUTHWEST REGION**
PROJECT NUMBER: **STPG SIGN(32)**

FILE NAME: **STOCKBRIDGE EB.XLS** PLOT DATE: **7/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **J. KELLY**
DESIGNED BY: **J. KELLY** CHECKED BY: **A. GAMBLE**
STOCKBRIDGE EASTBOUND SHEET 2 SHEET **78** OF **90**