DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOCKBRIDGE VT-107							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	3.240	A	W1-6	48	24		LEFT LARGE ARROW			1				X														
EB	3.245	A	OM-3R	12	36		RIGHT OBJECT MARKER			1				X														
EB	3.280	B	OM-3L	12	36		LEFT OBJECT MARKER			1				X														
EB	3.298	B	W1-6	48	24		LEFT LARGE ARROW			1				X														
EB	3.320	A	R2-1	24	30		SPEED LIMIT 50			1				X														
EB	3.980	A	W1-10R	36	36		MODIFIED RIGHT CURVE			1				X														
		A	W13-1	24	24		35 MPH ADVISORY			1																		
EB	4.110	C	VR-017	24	30								1		X												MT. HUNGER RD. (TH-15)			
		C	VR-017	24	30			5.00								1		15.0 X									4	
EB	4.125	D	R1-1	30	30								1		X												MT. HUNGER RD. (TH-15)			
		D	N/A	24	18		NO LEFT TURN				1		1																
		D	R1-1	30	30			6.25								1		14.0 X									X	
		D	N/A	24	18		NO LEFT TURN					1															REINSTALL SIGN BELOW NEW STOP SIGN.			
EB	4.209	A	VD-062B	72	16		BUSINESS SIGN			1				X														
		A	VD-062AS	72	16		BUSINESS SIGN			1																		
							SHEET TOTALS	11.25	0.00	9	1	1	~~2~~ 3	0	0	2			~~30~~ 29.0									
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT									
							TOWN DIRECTIONAL TOTALS	131.8	0.0	24.0	1.0	1.0	23	0.0	0.0	19			285.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: STOCKBRIDGE EB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
STOCKBRIDGE EASTBOUND SHEET 4

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE