DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOCKBRIDGE VT-107							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W13-1	18	18		35 MPH ADVISORY						1															
		F	VW-619	36	36			9.00								2		15.0 ~~15.75~~ X											
WB	4.160	F	W1-2LM	36	36	FY		9.00								2		15.25 ~~16.25~~ X								INSTALL 200 FEET WEST OF EXISTING LEFT CURVE SIGN ASSEMBLY.		6	
		F	W13-1	18	18	FY		2.25																			X		
WB	4.102	F	W1-6	48	24		LEFT LARGE ARROW			1				X															
		E	W1-6	48	24		RIGHT LARGE ARROW			1																			
WB	4.042	F	W1-6	48	24		LEFT LARGE ARROW			1				X															
		E	W1-6	48	24		RIGHT LARGE ARROW			1																			
WB	3.460	F	W1-4L	30	30		LEFT REVERSE CURVE			1				X															
		F	W13-1	18	18		40 MPH ADVISORY			1																			
WB	3.371	F	W2-2L	30	30		LEFT SIDE ROAD			1				X															
WB	3.370	F	W8-5	30	30		SLIPPERY WHEN WET			1																			
WB	3.275	F	OM-3R	12	36		RIGHT OBJECT MARKER			1				X															
WB	3.240	E	OM-3L	12	36		LEFT OBJECT MARKER			1				X															
WB	3.150	F	S4-3	24	8		SCHOOL			1				X															
							SHEET TOTALS	20.25	0.00	11	0	0	1	0	0	4		~~60~~ 62.25											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	151.3	0.0	22.0	0.0	0.0	35	0.0	0.0	20		300.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: STOCKBRIDGE WB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
STOCKBRIDGE WESTBOUND SHEET 2

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE
SHEET 83 OF 90