DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
STOCKBRIDGE VT-107							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	3.150	F	R2-1	24	30		SPEED LIMIT 35			1																		
WB	3.150	F	S4-4	24	10		WHEN FLASHING			1																		
WB	3.095	F	S1-1	30	30		SCHOOL			1				X														
WB	2.960	G	VR-017	24	30								1		X												SCHOOL DRIVE			
		G	VR-017	24	30			5.00								1		13.25 X										4	
WB	2.950	H	R1-1	30	30								1		X												SCHOOL DRIVE			
		H	R1-1	30	30			6.25								1		13.0 X										X	
WB	2.930	G	VR-017	24	30								1		X												SCHOOL DRIVE			
		G	VR-017	24	30			5.00								1		13.25 X										4	
WB	2.920	H	R1-1	30	30								1		X												SCHOOL DRIVE			
		H	R1-1	30	30			6.25								1		13.25 X										X	
WB	2.725	F	S5-2	24	30		END SCHOOL ZONE			1				X														
WB	2.655	G	VR-017	24	30								1		X												BLACKMORE BLVD. (TH-1)			
		G	N/A	24	30		NO THRU TRUCKS						1													RETURN SIGN TO TOWN			
		G	VR-017	24	30			5.00								1		14.0 X										4	
SIGN SUMMARY SHEET							SHEET TOTALS	27.50	0.00	4	0	0	6	0	0	5		~~75~~ 66.75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	151.3	0.0	22.0	0.0	0.0	35	0.0	0.0	20		300.0										

PROJECT NAME: STATEWIDE - SOUTHWEST REGION
PROJECT NUMBER: STPG SIGN(32)

FILE NAME: STOCKBRIDGEWB.XLS
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: J. KELLY
STOCKBRIDGE WESTBOUND SHEET 3

PLOT DATE: 7/13/2010
DRAWN BY: J. KELLY
CHECKED BY: A. GAMBLE