

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY (VT)	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							580				580		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							10		170		180		CWT	EMULSIFIED ASPHALT	404.65				
							90		2630		2720		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27				
									1		1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	406.29				
									1		1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									25		25		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
									430		430		GAL	WATER REPELLENT, SILANE	514.10				
									17810		17810		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									450		450		LF	JOINT SEALER, POLYURETHANE	524.21				
									400		400		LF	REMOVAL OF EXISTING RAILING	525.10				
									400		400		LF	RESETTING RAILING	525.11				
							90		17805		17895		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
									3		3		EACH	PARTIAL REMOVAL OF STRUCTURE (EXPANSION JOINT, 3 SEALS)	529.20				
									2		2		EACH	PARTIAL REMOVAL OF STRUCTURE (EXPANSION JOINT, 4 SEALS)	529.20				
									535		535		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
									1785		1785		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
									145		145		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
									160220		160220		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
									100		100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
									5720		5720		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
									41		41		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
									1250		1250		LF	TEMPORARY TRAFFIC BARRIER	621.90				
									4950		4950		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
									1450		1450		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
									10600		10600		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10				
									1		1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
									1		1		LS	TRAFFIC CONTROL	641.10				
									2		2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							300		8120		8420		LF	4 INCH WHITE LINE	646.20				
							300		8120		8420		LF	4 INCH YELLOW LINE	646.21				
									48250		48250		LF	TEMPORARY 4 INCH WHITE LINE, TYPE II TAPE	646.601				
									27700		27700		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602				
									48250		48250		LF	TEMPORARY 4 INCH YELLOW LINE, TYPE II TAPE	646.611				
									27700		27700		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612				