



KOR-N-SEAL® II FLEXIBLE CONNECTOR

Installation Chart



18" HOPE

Connector P/N	Suggested Pipe O.D. Range Inches	Hole Size Range Inches	Connector Dimensions Inches			Pipe Clamp		
			A	B	C	D	Qty	P/N
S206-18L	15.000 — 15.625	17.98 — 18.13		15.875	16	10.50	2	I-282
S206-22	17.625 — 19.000	21.98 — 22.13		19.875	19	10.50	2	I-318
S206-22L	19.000 — 19.625		20		2		I-348	
*S206-24A	18.000 — 19.500	23.98 — 24.13		21.875	18.75	12.00	4	I-180
S206-24	19.625 — 21.000	23.98 — 24.13		21.875	21	10.50	4	I-180
S206-24L	21.000 — 21.625		22		4			
S206-26	21.625 — 23.000	26.00 — 26.20		23.875	23	10.50	4	I-190
S206-26L	23.000 — 23.625		24		4		I-218	
S206-28	23.625 — 25.000	28.00 — 28.20		25.875	25	10.50	4	I-218
S206-28L	25.000 — 25.625		26		4			
S206-30	25.625 — 27.000	30.00 — 30.20		27.875	27	10.50	4	I-218
S206-30L	27.000 — 27.625		28		4		I-242	
S206-32	27.625 — 29.000	32.00 — 32.20		29.875	29	10.50	4	I-242
S206-32L	29.000 — 29.625		30		4			
S206-34	29.625 — 31.000	34.00 — 34.20		31.875	31	10.50	4	I-258
S206-34L	31.000 — 31.625		32		4			
S206-36	31.625 — 33.000	36.00 — 36.20		33.875	33	10.50	4	I-282
S206-36L	33.000 — 33.625		34		4			
S206-38	33.625 — 35.000	38.00 — 38.20		35.875	35	10.50	4	I-282
S206-38L	35.000 — 35.625		36		4		I-306	
S206-40	35.625 — 37.000	40.00 — 40.20		37.875	37	10.50	4	I-306
S206-40L	37.000 — 37.625		38		4			
S206-42	37.625 — 39.000	42.00 — 42.20		39.875	39	10.50	4	I-318
S206-42L	39.000 — 39.625		40		4		I-348	
S206-44	39.625 — 41.000	44.00 — 44.20		41.875	41	10.50	4	I-348
S206-44L	41.000 — 41.625		42		4			
S206-46	41.625 — 43.000	46.00 — 46.20		43.875	43	10.50	4	I-348
S206-46L	43.000 — 43.625		44		6		I-242	
S206-48	43.625 — 45.000	48.00 — 48.20		45.875	45	10.50	6	I-242
S206-48L	45.000 — 45.625		46		6		I-258	
S206-50	45.000 — 45.625	50.00 — 50.25		47.250	46	10.50	6	I-258
S206-50L	45.625 — 47.000		47		6			
S206-52	47.000 — 47.625	52.00 — 52.25		49.250	48	10.50	6	I-282
S206-52L	47.625 — 49.000		49		6			
S206-54	49.000 — 49.625	54.00 — 54.25		51.250	50	10.50	6	I-282
S206-54L	49.625 — 51.000		51		6			

* Molded

- Double Wedge is available for 22 to 48 inch sizes, but .500 inches must be subtracted from the "B" dimension thus limiting your pipe O.D. range by .500 inches. The Double Wedge is only available on the "L" connectors.
- Special sizes quoted upon request.
- 50 inch (or larger) Connectors have 2 Wedges or more.

Caution:

- All stubs awaiting pipe installation at a later date must be restrained.
- Assure that a proper backfill material is used in adverse conditions.
- Prior to any critical usage, contact NPC Customer Service 800-626-2180.



Manufactured under the following patents:
 U.S. 5,431,459 CAN. 2,004,749
 EU/GERMANY: EP049811B

www.npc.com

250 Elm Street • P.O. Box 301
 Milford, NH 03055, U.S.A.

Tel: 603-673-8680 • 800-626-2180 • Fax: 603-673-7271