




## NEMA P-44 Traffic Control Cabinet



**Highway Tech** Signal Equipment Sales, Inc.  
8 Gardiner Road / P.O. Box 1209  
Sabattus, ME 04280  
Tel. (207) 375-8248  
Fax (207) 375-8279

### Features

- Meets NEMA standards
- Base mounted
- Constructed of 0.125" thick aluminum
- "C" mounting channels on side and back walls for mounting shelves and panels
- 3-point latching mechanism of zinc plated steel
- Stainless steel door handle designed for padlock
- Stainless steel door hinge
- Optional Lifting Ears

### SPECIFICATIONS:

Outside dimensions: 55" H x 44" W x 26" deep  
Opening Dimensions: 53" H x 41" W  
Mounting Pattern 40.50" W x 18.50" D

Material: Aluminum (.125" thick)  
Finish: Bare or Painted  
Mounting: Base Mounted  
Locking System: 3-point locking system with Corbin #2 lock  
Door Stops: Three position bar stop at bottom of door  
Ventilation: Pleated fiber filter in door, fan with thermostatic control  
Light: Incandescent or optional flourescent, door switch activated

### Technology That Moves America

Naztec, Inc. • 820 Park Two Drive • Sugar Land, Texas 77478 • Phone (281) 240-7233 • Fax (281) 240-7238

Email: [naztec@naztec.com](mailto:naztec@naztec.com) • <http://www.naztec.com>