




## MMU 516 Malfunction Management Unit RS232

### FEATURES

- Meets and exceeds all TS2 specifications
- High speed internal data transfer and communications via an SDLC port
- High speed external data transfer via an RS-232 port
- Tri-Color LEDs Red, Yellow, Green for channel display
- LED indicator lamps for operation analysis
- Removable program card
- High performance machine tooled sockets for integrated circuit mounting



**Highway Tech** Signal Equipment Sales, Inc.  
8 Gardiner Road / P.O. Box 1209  
Sabattus, ME 04280  
Tel. (207) 375-8248  
Fax (207) 375-8279

The Naztec Model MMU 516 Malfunction Management Unit is an enhanced MMU that monitors up to 16 traffic signal indications (channels) for conflict, improper sequencing, incorrect timing, and improper signal voltage levels. The MMU 516 is fully compliant with NEMA Standard TS2-1992. The MMU 516 is also capable of operating in older TS1 type cabinets, and is compatible with 12-channel Conflict Monitor Units conforming to the NEMA Standard TS1-1989.

All connectors, indicators and operator controls are located on the front panel of the MMU 516. Channel and control input signals and relay output connections are made through two MIL-C-26482 connectors, and the SDLC Port is an A-size, 15 contact, D shell connector. The RS232 Port is excellent for tracking important phase output data back to the controller or to a PC for logging. The programming card and the AC line fuse are easily accessed from the front panel.

The MMU 516 provides a Reset Timeout feature to prevent a broken switch or accidental wiring fault from holding the unit in the reset state for an extended period of time. LED indicators, in addition to the TS2 specified indicators, include Dual Indication Fault, Yellow+Red Clearance Fault, Programming Card Ajar, Field Check (active channels do not match SDLC message from controller) Fault, and LEDs for two +24VDC input faults and CVM input faults. Status indicators provided include: AC Line Power, Type 12 Indicator, SDLC Transmitter Active, and SDLC Msg Received.

For added safety, the MMU 516 performs continuous diagnostic tests during all operating modes. All memory elements, the microprocessor, operating voltages, and critical circuitry are checked.

**820 Park Two Drive Sugar Land, TX 77478 (281) 240-7233**  
**www.naztec.com naztec@naztec.com Additional Offices in Florida and Virginia**