



Technical Specifications

Mounting

- Rotational axes: 2
 - NOTE: SmartSensor Advance and SmartSensor Matrix are shipped with rotational backplate for third axis of rotation. SmartSensor V and SmartSensor HD can be ordered with rotational backplate if third axis is required.
- Maximum load: 15 lbs. (6.8 kg)
- Symmetric hole pattern that mates with fixed and rotational SmartSensor backplates
- Contact points with pole: 2
- Slotted for 3/4-in. (1.9-cm) banding

Construction

- Constructed of aluminum 0.1875 in. (0.48 cm) thick
- 316 stainless steel hardware
- Powder coated
- Weight: 3 lbs. (1.36 kg)

Ordering Information

SmartSensor mount
SS-611

Wavetronix

78 East 1700 South
Provo, UT 84606

801.734.7200

sales@wavetronix.com

www.wavetronix.com