





Traffic Signals (8"/12" PC/AL)

Four screw visor attachment
(threaded brass inserts on
poly doors)



8" Al Signal

"Tab" Visor




Self draining heavily
ribbed end sections
with integral shurlock

Captive wing nut
style door latch
assemblies

Backplate mounting
holes (4 per section)

Stainless steel reflector
ring hinge pins


Door Gasket
One piece molded EPDM lens
gasket (Silicone available)



Alzak Reflector

Stainless Steel lens tabs;
(threaded brass inserts on
poly doors)

All external
hardware is
stainless steel



Reinforcing fins in poly head

Reflector Gasket

Fully insulated quick connect
socket wire terminals

Color coded socket wires

Rotatable high temperature
phenolic socket with lamp grip
and gasket

Aluminum reflector ring

Meets/Exceeds ITE Specifications

1-800-345-6329