

Advisor Guide Accessible Pedestrian Station (AGPS)



FEATURES

- Data Collection
- Night Mode Volume
- Forward Facing Speaker
- Simple Installation

KEY BENEFITS

- Independent Locations
- 4-wire Interface
- Event Tracking Log
- Ped Count/Call Data
- Laptop Interface
- Simple Menu Utility
- NEMA TS 2 Certified
- Meets MUTCD Guidelines



Overview

Regardless of physical capability, pedestrians are finding it more challenging to cross safely at signalized intersections. The Advisor APS provides important cues to assist all pedestrians to cross the intersection safely by providing audible, tactile, and visual indications at the crosswalk.

Independent Station

A locator tone, controlled with ambient gain compensation, tells a pedestrian that the crossing is equipped with APS and where it can be found. An extended press provides specific intersection information and access to additional functions. The audible walk tone or message is accompanied by a vibro-tactile indication during the visual walk display. Optional clearance phase indications may provide additional information to the pedestrian where appropriate.

Agency Benefits

The Advisor (AGPS) is designed around flexibility and ease of use. Each Advisor is configured at the factory, but customization and data extraction are simply obtained by utilizing any laptop with a USB connection. A menu driven utility guides the user through set up and downloads effortlessly. Night mode volume controls along with forward facing speakers incorporate Quiet Signals Technology to accommodate residential and evening business considerations.

Installation

Ready to mount, out of the box, a four conductor cable interfaces to the Signal Power Interface (SPI) in the pedestrian signal head. All adjustments and settings are made at the pedestrian station. Aesthetically pleasing extension brackets are available allowing stations to be mounted within accessibility guidelines.