

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						260					260		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
						4					4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						4					4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72				
						170					170		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						640					640		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						2					2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						1050					1050		LF	4 INCH WHITE LINE	646.20				
						1050					1050		LF	4 INCH YELLOW LINE	646.21				
						140			560		700		SY	GEOTEXTILE UNDER STONE FILL	649.31				
						260					260		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41				
								230			230		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								90			90		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								70			70		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								20			20		LB	SEED	651.15				
								20			20		LB	SEED, WINTER RYE	651.17				
								100			100		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								50			50		CY	TOPSOIL	651.35				
									80		80		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								50			50		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								260			260		SY	TEMPORARY EROSION MATTING	653.20				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								620			620		LF	BARRIER FENCE	653.50				
								420			420		LF	PROJECT DEMARCATION FENCE	653.55				
						1					1		SF	TRAFFIC SIGNS, TYPE A	675.20				
						16					16		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
									20		20		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608				
						30					30		CY	SPECIAL PROVISION (STONE DIAPHRAGM)	900.608				
						8					8		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
						1					1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				

PROJECT NAME: BRISTOL
 PROJECT NUMBER: BRF 021-1(29)
 FILE NAME: si0b094qs.dgn PLOT DATE: 04-NOV-2014
 PROJECT LEADER: C. CARLSON DRAWN BY: R. PELLETT
 DESIGNED BY: M. EVANS-MONGEON CHECKED BY: EVANS-MONGEON
 QUANTITY SHEET (2) SHEET 8 OF 54