

## SUMMARY OF QUANTITIES BY ROUTE

ROUTE	TOWN	MM	TO	MM	4" WHITE LINE	MAT.	4" YELLOW LINE	MAT.	8" WHITE LINE	MAT.	8" YELLOW LINE	MAT.	STOP BAR	MAT.	LETTER OR SYM.	MAT.	CROSS WALK	MAT.	REMOVAL	REMARKS
US 7	POWNAI	0.00	-	7.99	86,624	PAINT	79,694	PAINT	-	-	1,200	PAINT	-	-	60	PAINT	-	-	-	ARROW(12) ONLY(9) SCHOOL(2)
US 7	BENNINGTON	0.00	-	2.16	22,810	PAINT	22,810	PAINT	-	-	-	-	-	-	-	-	-	-	-	
US 7	DORSET	1.75	-	6.72	53,084	PAINT	31,404	PAINT	-	-	500	PAINT	-	-	25	PAINT	-	-	-	ARROW(5) ONLY(5)
US 7	MT TABOR	0.00	-	4.18	44,140	PAINT	21,650	PAINT	-	-	-	-	-	-	-	-	-	-	-	
US 7	DANBY	0.00	-	2.47	26,084	PAINT	16,834	PAINT	-	-	-	-	-	-	-	-	-	-	-	
US 7	WALLINGFORD	0.00	-	6.48	67,494	PAINT	62,536	PAINT	-	-	-	-	22	PAINT	-	-	60	PAINT	-	
US 7	WALLINGFORD/RUTLAND TOWN	6.48	-	1.18																SEE ROUTE QUANTITIES SHEET 5
US 7	RUTLAND TOWN	1.18	-	3.97	30,938	PAINT	27,444	PAINT	350	PAINT	-	-	50	PAINT	51	PAINT	-	-	-	ARROW(5) ONLY(3) DBLARROW(6) SIGNAL(2) AHEAD(2)
US 7	PITTSFORD	0.00	-	7.59	81,796	PAINT	74,430	PAINT	325	PAINT	600	PAINT	-	-	43	PAINT	80	PAINT	-	ARROW(7) ONLY(6) SCHOOL(2)
US 7	BRANDON	0.00	-	0.70	44,930	PAINT	35,505	PAINT	-	-	700	PAINT	-	-	29	PAINT	-	-	-	ARROW(7) ONLY(4) SCHOOL(1)
US 7	BRANDON	4.35	-	7.45																BRANDON 0.70-BRANDON 3.36 2010 PROJECT
US 7	LEICESTER	0.00	-	3.43	36,220	PAINT	22,630	PAINT	-	-	-	-	-	-	12	PAINT	-	-	-	SCHOOL(2)
US 7	SALISBURY	0.00	-	4.50	47,520	PAINT	31,825	PAINT	-	-	-	-	-	-	-	-	-	-	-	
US 7	MIDDLEBURY	0.00	-	4.28	64,557	PAINT	51,712	PAINT	190	PAINT	1,675	PAINT	96	PAINT	109	PAINT	120	PAINT	-	ARROW(19) ONLY(13) DBLARROW(2) SIGNAL(2) AHEAD(2) SCHOOL(2)
US 7	MIDDLEBURY	5.71	-	7.48																
US 7	NEW HAVEN	0.00	-	6.10	67,066	PAINT	51,486	PAINT	-	-	800	PAINT	-	-	18	PAINT	-	-	-	ARROW(4) ONLY(3) RRXING(2)
US 7	NEW HAVEN	6.10	-	7.70	133,584	PAINT	46,755	PAINT	-	-	-	-	-	-	-	-	-	-	-	SEE NOTE BELOW
US 7	WALTHAM	0.00	-	1.64																ARROW(21) ONLY(15) SIGNAL(2) AHEAD(3) SCHOOL(2)
US 7	FERRISBURGH	0.00	-	7.29					200	PAINT	-	-	116	PAINT	132	PAINT	-	-	-	YIELD(1) YIELDMARKINGS(5) RRXING(2)
US 7	CHARLOTTE	0.00	-	6.55	72,243	PAINT	51,953	PAINT	-	-	925	PAINT	80	PAINT	60	PAINT	-	-	108	ARROW(6) ONLY(5) DBLARROW(6) SIGNAL(2) AHEAD(2)
US 7	SHELBURNE	0.00	-	2.60	29,631	PAINT	28,621	PAINT	-	-	1,200	PAINT	52	PAINT	128	PAINT	100	PAINT	-	ARROW(20) ONLY(16) SIGNAL(4) AHEAD(4)
US 7	SO. BURLINGTON	0.98	-	1.72	9,120	PAINT	15,000	PAINT	450	PAINT	250	PAINT	384	PAINT	98	PAINT	275	PAINT	1,764	REMOVAL=REALIGNING ARROW'S AND ONLY'S TO 2009 MUTCD
	US 7 TOTALS				917,841		672,289		1,515		7,850		800		765		635		1,872	
	PROJECT TOTALS				2,743,671		2,271,260		4,065		14,085		1,040		1,228		1,079		2,122	

NOTE: MAT. = MATERIAL USED FOR PAVEMENT MARKING  
 PAINT=PAINT  
 POLY=POLYUREA

NOTE: MM 6.10 NEW HAVEN-MM 7.29 FERRISBURGH  
 2008 PROJECT PAINT ALL WHITE E/L AND LANE LINES,  
 STENCIL'S AND APPROX. 35% OF YELLOW C/L.

**ROUTE QUANTITIES**  
**SHEET 4**

PROJECT: <b>STATEWIDE</b>	PROJECT NO.: <b>NHG MARK (204)</b>
DESIGN FILE NAME: I0b096.dgn	
IPARM FILE NAME: I0b096rq4.i	
SURVEYED BY:	
SQUAD LEADER: A GAMBLE	
PLOT DATE: 24-MAY-2010	
SURVEY DATE:	
DRAWN BY: KAS	
SHEET: 6 OF 24	