SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	4" WHITE LINE	8" YELLOW LINE	8" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	REMOVAL	REMARKS
US 2	EAST MONTPELIER	2.95	STOP(1)	-	-	-	20 FEET	4	-	-	JCT VT 14 NB
US 2	EAST MONTPELIER	3.16	STOP(1) AHEAD(1)	-	-	-	-	9	-	-	
US 2	PLAINFIELD	1.00	CROSSWALK	-	-	-	-	-	26 FEET	-	PLAINFIELD HEALTH CENTER
US 2	MARSHFIELD	7.88	ARROW(2) ONLY(1)	190 FEET	-	-	-	6	-	-	JCT VT 232
US 2	DANVILLE	1.73	CROSSWALK	-	-	-	-	-	32 FEET	-	WEST DANVILLE STORE
US 2	DANVILLE	4.20	SCHOOL(1)	-	-	-	-	6	-	-	
US 2	DANVILLE	4.30	CROSSWALK	-	-	-	-	-	33 FEET	-	
US 2	DANVILLE	4.40	SCHOOL(1)	-	-	-	-	6	-	-	
US 2	DANVILLE	4.45	CROSSWALK	-	-	-	-	-	33 FEET	-	
US 2	DANVILLE	4.53	SCHOOL(1)	-	-	-	-	6	-	-	
US 2	ST JOHNSBURY	6.54	YIELD MARKINGS(5)	-	-	325 FEET	-	5	-	72 FEET	JCT VT 18 REMOVAL=YIELD LETTERS
US 2	LUNENBURG	4.45	SCHOOL(1)	-	-	-	-	6	-	-	TO YIELD MARKINGS
US 2	LUNENBURG	4.62	CROSSWALK	-	-	500 FEET	-	-	35 FEET	-	
US 2	LUNENBURG	4.70	CROSSWALK	-	-	-	-	-	35 FEET	-	
US 2	LUNENBURG	4.85	SCHOOL(1)	-	-	-	-	6	-	-	
	TOTAL US 2			190 FEET	-	825 FEET	20 FEET	54	194 FEET	72 FEET	

HAND WORK

QUANTITIES SHEET 3

PROJECT: **STATEWIDE**

PROJECT NO.: **NH⊕ MARK (204)**

DESIGN FILE NAME: 10b096.dgn
IPARM FILE NAME: 10b096hw3.i
SURVEYED BY:
SQUAD LEADER: A GAMBLE

PLOT DATE: 24-MAY-2010
SURVEY DATE:
DRAWN BY: KAS
SHEET: 10 OF 24