SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	4" WHITE LINE	8" YELLOW LINE	8" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	REMOVAL	REMARKS
US 7	SO. BURLINGTON	1.53	ARROW(6) ONLY(3)	300 FEET	-	-	84 FEET	18	-	510 FEET	JCT K-MART
US 7	SO. BURLINGTON	1.58	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.61	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.63		-	-	350 FEET	-	-	-	-	DO NOT BLOCK INTERSECTION
US 7	SO. BURLINGTON	1.64	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.65		-	150 FEET	-	24 FEET	-	-	-	
US 7	SO. BURLINGTON	1.67		-	-	-	-	-	75 FEET	-	
US 7	SO. BURLINGTON	1.69	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7	SO. BURLINGTON	1.70	DBL ARROW(2)	-	-	100 FEET	-	4	-	-	
US 7	SO. BURLINGTON	1.72	DBL ARROW(2)	100 FEET	100 FEET	-	36 FEET	4	-	-	
	TOTAL US 7			11,560 FEET	7,850 FEET	1,515 FEET	800 FEET	767	585 FEET	1,872 FEET	

HAND WORK

QUANTITIES SHEET 6

PROJECT: **STATEWIDE**

PROJECT NO.: **NHG MARK (204)**

DESIGN FILE NAME: 10b096.dgn
IPARM FILE NAME: 10b096hw6.I
SURVEYED BY:
SQUAD LEADER: A GAMBLE

PLOT DATE: 24-MAY-2010
SURVEY DATE:
DRAWN BY: KAS
SHEET: 13 OF 24