SUMMARY OF HAND WORK BY ROUTE

ROUTE	TOWN	MM	STENCIL	6" WHITE LINE	12" YELLOW LINE	12" WHITE LINE	STOP BAR	LETTER & SYM.	CROSS WALK	REMOVAL	REMARKS
US 7 NB	RUTLAND TOWN	1.03	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7 NB	RUTLAND TOWN	1.06	ARROW(2)	-	-	-	-	2	-	-	TWO-WAY TURN LANE ARROWS
US 7 NB	RUTLAND TOWN	1.14	ARROW(2) ONLY(1)	125 FEET	-	-	36 FEET	6	-	-	JCT COLD RIVER RD
US 7 SB	RUTLAND TOWN	1.14	ARROW(2) ONLY(1)	125 FEET	-	-	36 FEET	6	-	-	JCT COLD RIVER RD
			US 7 RUTLAND TOWN TOTALS	3,730 FEET	-	-	408 FEET	150	120 FEET	-	
			US 7 CLARENDON TOTALS	5,275 FEET	-	900 FEET	254 FEET	342	-	-	
			US 7 TOTALS	9,005 FEET	-	900 FEET	662 FEET	492	120 FEET	-	
	US 2										
US 2 WB	ST JOHNSBURY	1.16	ARROW(2) ONLY(2) STOP(2)	360 FEET	-	-	24 FEET	18	-	-	JCT TH 7
US 2 EB	ST JOHNSBURY	1.69				270 FEET					JCT I-91 SB ON RAMP(RAMP A)
US 2 WB	ST JOHNSBURY	1.86				235 FEET					JCT I-91 SB ON RAMP(RAMP E)
US 2 EB	ST JOHNSBURY	1.88	STOP(1)	-	-	-	18 FEET	4	-	-	IN MEDIAN AT SB OFF RAMP (RAMP H)
US 2 EB	ST JOHNSBURY	1.93				250 FEET					JCT I-91 SB OFF RAMP(RAMP C)
US 2 EB	ST JOHNSBURY	2.02				235 FEET					JCT I-91 NB OFF RAMP(RAMP D)
US 2 WB	ST JOHNSBURY	2.07	STOP(1)	-	-	-	18 FEET	4	-	-	IN MEDIAN AT NB OFF RAMP (RAMP G)
US 2 WB	ST JOHNSBURY	2.19				535 FEET					JCT I-91 NB ON RAMP(RAMP F)
US 2 EB	ST JOHNSBURY	2.31				250 FEET					JCT I-91 NB ON RAMP(RAMP B)
US 2 EB	ST JOHNSBURY	2.62	ARROW(3) ONLY(3)	430 FEET	-	-		15	-	-	JCT VT 2B
US 2 WB	ST JOHNSBURY	2.62	ARROW(2) ONLY(1)	175 FEET	-	-		6	-	-	JCT VT 2B
			US 2 TOTALS	965 FEET		1,775 FEET	60 FEET	47			

HAND WORK

QUANTITIES SHEET 8

PROJECT: **STATEWIDE**

PROJECT NO.: **NHG MARK (204)**

DESIGN FILE NAME: 10b096.dgn
IPARM FILE NAME: 10b096hw8.I
SURVEYED BY:
SQUAD LEADER: A GAMBLE

PLOT DATE: 24-MAY-2010
SURVEY DATE:
DRAWN BY: KAS
SHEET: 15 OF 24