QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						BEGIN ITEMS COMMON TO ALL ALTERNATES		
		110 500		110 500	LF	SHOULDER BERM REMOVAL	203.40	230
		1		1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
		26 000		26 000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	396
		1		1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		80 000		80 000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690)TYPE II)	417.20	395
	1400			1400	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	4
	100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COURSE AGGREGATE	580.20	EST
		300		300	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
		2 000		2 000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
		1200		1200	HR	FLAGGERS	630.15	EST
			1	1	LS	FIELD OFFICE, ENGINEERS	631.10	
			1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3 000	3 000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
520				520	HR	EMPLOYEE TRAINEESHIP	634.10	-
		1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
		1		1	LS	TRAFFIC CONTROL	641.10	
		4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		530 000		530 000	LF	6 INCH WHITE LINE	646.214	2846
		435 000		435 000	LF	6 INCH YELLOW LINE	646.215	4582
		6 000		6 000	LF	12 INCH WHITE LINE	646.24	EST
		350		350	LF	24 INCH STOP BAR	646.26	20
		195		195	EA	LETTER OR SYMBOL	646.30	EST
		4		4	EA	RAILROAD CROSSING SYMBOL	646.32	-
		265 000		265 000	LF	TEMPORARY 6 INCH WHITE LINE	646.620	1423
		220 000		220 000	LF	TEMPORARY 6 INCH YELLOW LINE	646.630	4791
		6 000		6 000	LF	TEMPORARY 12 INCH WHITE LINE	646.660	EST.
		350		350	LF	TEMPORARY 24 INCH STOP BAR	646.680	20
		108		108	EA	TEMPORARY LETTER OR SYMBOL	646.690	EST.
		4		4	EA	TEMPORARY RAILROAD CROSSING SYMBOL	646.710	
		10 250		10 250	EA	LINE STRIPING TARGETS	646.76	33
		241 000		241 000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	550
		1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
		1		1	LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC)(N.A.B.I.)	900.650	-
		30		30	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
						END ITEMS COMMON TO ALL ALTERNATES		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BEGIN ALTERNATE A
		COLD PLANING, BITUMINOUS PAVEMENT
150	SY	BEGIN PROJECT
150	SY	END PROJECT
20 664	SY	BRIDGES
3 690	SY	INTERCHANGES
350	SY	U-TURNS
600	SY	RAILROAD CROSSING
25 604	SY	SUBTOTAL
396	SY	ROUNDING
26 000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN-RUTLAND TOWN
PROJECT NUMBER: NH SURF (22)

FILE NAME: 10b106\10b106.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: PVT. MGT.
IPARM FILE NAME: 10B106*5.i

PLOT DATE: 23-MAY-2013 11:41
DRAWN BY: PVT. MGT.
CHECKED BY: PVT. MGT.
SHEET 5 OF 24