QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						BEGIN ALTERNATE A		
		645 000		645 000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	3570
						END ALTERNATE A		
						BEGIN ALTERNATE B		
		1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		38 000		38 000	TON	SPECIAL PROVISION (6.3 MM POLYMER - MODIFIED BITUMINOUS CONCRETE PAVEMENTX SBR OR SBS POLYMER)	900.680	463
		4 500		4 500	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	39
						END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
294 782	SY	MAINLINE--EB
288 462	SY	MAINLINE--WB
57 957	SY	INTERCHANGES
229	SY	END PROJECT RAMPS
641430	SY	SUBTOTAL
3570	SY	ROUNDING
645 000	SY	TOTAL
		END ALTERNATE A
		BEGIN ALTERNATE B
		BITUMINOUS CONCRETE PAVEMENT)
		SPECIAL PROVISION (6.3 MM POLYMER - MODIFIED (SBR OR SBS POLYMER)
17 196	TON	MAINLINE-EB
16 827	TON	MAINLINE-WB
3 381	TON	INTERCHANGES
133	TON	END PROJECT RAMPS
37 537	TON	SUBTOTAL
463	TON	ROUNDING
38 000	TON	TOTAL
		END ALTERNATE B

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN-RUTLAND TOWN
PROJECT NUMBER: NH SURF (22)

FILE NAME: 10b106\10b106.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: PVT. MGT.
IPARM FILE NAME: 10B106*6.i

PLOT DATE: 23-MAY-2013 11:41
DRAWN BY: PVT. MGT.
CHECKED BY: PVT. MGT.
SHEET 6 OF 24