



TYPICAL SECTION
MM 3.745 (DORSET) – MM 2.473 (DANBY)

NOTES:

1. ALL NECESSARY SURFACE PREPARATION INVOLVING PATCHING, POT HOLE REPAIR, AND CRACK SEALING SHALL BE PERFORMED PRIOR TO APPLICATION OF ANY SPOT LEVELING OR PLACEMENT OF THE WEARING COURSE. ALL CRACKS GREATER THAN 0.10 INCH AND UP TO 1.0 INCH IN WIDTH SHALL BE SEALED USING THE "BLOW AND GO" FILL METHOD. ALL COSTS ASSOCIATED WITH THIS WORK SHALL BE PAID FOR UNDER ITEM 417.20, BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD. THE PATCHING OF ALL CRACKS GREATER THAN 1.0 INCH AND ALL OTHER PATCHING AND POT HOLE REPAIR SHALL BE COMPLETED USING BITUMINOUS CONCRETE PAVEMENT IN ACCORDANCE WITH ITEM 900.680 SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I). AN ESTIMATED QUANTITY FOR THIS ITEM HAS BEEN INCLUDED TO COVER ALL COSTS ASSOCIATED WITH THIS WORK.

2. FOLLOWING COMPLETION OF COLD PLANING, THE MILLED SURFACE FOR ALL BRIDGES SHALL ALSO RECEIVE CRACK SEALING AND RELATED PATCHING AND POT HOLE REPAIR TREATMENTS, AS DIRECTED BY THE RESIDENT ENGINEER.

3. ALL EXISTING PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO ANY CRACK SEALING BEING PERFORMED AND PRIOR TO APPLYING THE PAVER PLACED SURFACE TREATMENT. ALL LANE DELINEATION IS TO BE MAINTAINED DURING CONSTRUCTION BY THE USE OF LINE STRIPING TARGETS OR TEMPORARY PAINT.

4. A 50' COLD PLANED WEDGE SHALL BE CONSTRUCTED AT THE PROJECT BEGIN, PROJECT END, AND AT ALL BRIDGE APPROACHES OR AS DIRECTED BY THE RESIDENT ENGINEER. ANY SAWCUTTING AT BUTT JOINTS SHALL BE PAID INCIDENTAL TO ITEM 210.10, COLD PLANING, BITUMINOUS PAVEMENT. THE CONTRACTOR SHALL USE CAUTION WHEN COLD PLANING AND PAVING OPERATIONS OCCUR ADJACENT TO EXISTING DROP INLETS OR CATCH BASINS. ANY DAMAGE WHICH OCCURS TO THESE DRAINAGE STRUCTURES AS A RESULT OF THESE OPERATIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE STATE OF VERMONT.

5. IF IT IS DETERMINED IN AREAS ALONG THE BASE OF THE GUARDRAIL THAT WINTER SAND AND OTHER DEBRIS HAS ACCUMULATED SUFFICIENTLY TO AFFECT PROPER CRACK SEALING AND RELATED PATCHING AND POT HOLE REPAIR TREATMENTS, THIS MATERIAL SHALL BE REMOVED PRIOR TO CRACK SEALING, PATCHING, AND POT HOLE REPAIR AS DIRECTED BY THE RESIDENT ENGINEER. AN ESTIMATED QUANTITY FOR ITEM 203.40 SHOULDER BERM REMOVAL HAS BEEN INCLUDED TO COVER THE COSTS ASSOCIATED WITH THIS WORK.

6. IT IS EXPECTED THAT SOME SPOT LEVELING WILL BE NECESSARY AS DIRECTED BY THE RESIDENT ENGINEER PRIOR TO THE PLACEMENT OF THE WEARING COURSE. AN ESTIMATED QUANTITY OF ITEM 900.680 SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) AND ITEM 900.683 SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-IH OR CRS-IH) HAS BEEN INCLUDED FOR THIS PURPOSE.

7. BRIDGES WITHIN THIS TYPICAL SECTION ARE:

- ~~BRIDGE NUMBER 54, MM 4.992 (DORSET) COMP. WF BEAM S (COLD PLANE 3/4" THEN PAVE WITH SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C))~~
- BRIDGE NUMBER 56C, MM 3.001 (MT. TABOR) COMP. WF BEAM ST (COLD PLANE 3/4" THEN PAVE WITH SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C))
- BRIDGE NUMBER 66, MM 1.564 (DANBY) CONC. SLAB CC (COLD PLANE 3/4" THEN PAVE WITH SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C))

NOT TO SCALE

**ALTERNATE A
TYPICAL
SECTION**

PROJECT NAME: DORSET - DANBY
 PROJECT NUMBER: NH SURF (24)

FILE NAME: I0b118\p10b118.dgn PLOT DATE: 23-MAY-2012 16:05
 PROJECT LEADER: FOWLER DRAWN BY: HUNT
 DESIGNED BY: HUNT CHECKED BY: PAVT MGMT
 IPARM FILE NAME: I0b118_03.i SHEET 3 OF 16