QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I)	690.50	-
	1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.))	900.650	-
	20		20	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
	1,000		1,000	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST
	1,300		**1,300**	**TON**	**SPECIAL PROVISION (9.5 MM SBS POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (0% RAP)** 1	**900.680**	**23**
	1,300		**1,300**	**TON**	**SPECIAL PROVISION (9.5 MM SBS POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (25% RAP)** 1	**900.680**	**46**
	335		335	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST
					END ITEMS COMMON TO ALL ALTERNATES		
					BEGIN ALTERNATE A		
	218,500		218,500	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	1,736
					END ALTERNATE A		
					BEGIN ALTERNATE B		
	1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	12,100		**12,100**	**TON**	**SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)** 1	**900.680**	**255**
	1,600		1,600	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	10
					END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (9.5 MM SBS POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (0% RAP)
1,277	**TON**	**MAINLINE**
1,277	**TON**	**SUBTOTAL**
23	**TON**	**ROUNDING**
1,300	**TON**	**TOTAL**
		SPECIAL PROVISION (9.5 MM SBS POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (25% RAP)
1,210	**TON**	**MAINLINE**
44	**TON**	**BRIDGE 52 & APPROACHES**
1,254	**TON**	**SUBTOTAL**
46	**TON**	**ROUNDING**
1,300	**TON**	**TOTAL** 1
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
213,753	SY	MAINLINE
1,322	SY	BRIDGE 54 & APPROACHES
950	SY	BRIDGE 56 & APPROACHES
739	SY	BRIDGE 66 & APPROACHES
216,764	SY	SUBTOTAL
1,736	SY	ROUNDING
218,500	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)
11,713	**TON**	**MAINLINE**
58	**TON**	**BRIDGE 54 & APPROACHES**
42	**TON**	**BRIDGE 56 & APPROACHES**
32	**TON**	**BRIDGE 66 & APPROACHES**
11,845	**TON**	**SUBTOTAL**
255	**TON**	**ROUNDING**
12,100	**TON**	**TOTAL** 1

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

1 – **REVISED 04 /26 /11 LSW**

PROJECT NAME: DORSET - DANBY
PROJECT NUMBER: NH SURF (24)

FILE NAME: 10b118\p10b118.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: HUNT
IPARM FILE NAME: 10b118_08.i

PLOT DATE: 23-MAY-2012
DRAWN BY: HUNT
CHECKED BY: PAVT MGMT