

QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
					ROADWAY	TRAINING	EROSION CONTROL	UTILITIES BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									383		383		CM	CONCRETE, CLASS C	541.30	1			
														BEGIN OPTION AA					
					23						23		M	375 CAAP 1.52 (68 X 12)	601.0210	-			
					23						23		M	375 PCCSP 1.63 (68 X 12)	601.0410	-			
														END OPTION AA					
														BEGIN OPTION BB					
					38.2						38.2		M	450 CAAP 1.52 (68 X 12)	601.0215	-			
					38.2						38.2		M	450 PCCSP 1.63 (68 X 12)	601.0415	-			
					38.2						38.2		M	450 PCCSP(PJ) 1.63 (68 X 12)	601.0615	-			
														END OPTION BB					
														BEGIN OPTION CC					
					381.2						381.2		M	450 RCP CLASS III	601.0815	-			
					381.2						381.2		M	450 CPEP(SL)	601.2615	-			
														END OPTION CC					
														BEGIN OPTION DD					
					48						48		M	750 RCP CLASS III	601.0835	-			
					48						48		M	750 CPEP(SL)	601.2625	-			
														END OPTION DD					
														BEGIN OPTION EE					
					14.5						14.5		M	900 RCP CLASS III	601.0845	-			
					14.5						14.5		M	900 CPEP(SL)	601.2630	-			
														END OPTION EE					
					15.7						15.7		M	450 CPEP(SL)	601.2615	-			
					18						18		M	750 CPEP(SL)	601.2625	-			
														BEGIN OPTION FF					
					2						2		EACH	450 CAAP ELBOW 1.52 (68 X 12)	601.5215	-			
					2						2		EACH	450 PCCSP ELBOW 1.63 (68 X 12)	601.5415	-			
														END OPTION FF					
					2						2		EACH	450 CPEP ELBOW (SL)	601.5814	-			
														BEGIN OPTION GG					
					1						1		EACH	375 CSPES 1.63 (68 X 12)	601.6010	-			
					1						1		EACH	375 CAAPES 1.52 (68 X 12)	601.6210	-			
														END OPTION GG					
														BEGIN OPTION HH					
					2						2		EACH	450 CSPES 1.63 (68 X 12)	601.6015	-			
					2						2		EACH	450 CAAPES 1.52 (68 X 12)	601.6215	-			
					2						2		EACH	450 RCPES CLASS III	601.6815	-			
					2						2		EACH	450 CPEPES	601.7015	-			
														END OPTION HH					
					12						12		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-			

PROJECT NAME: MORRISTOWN
 PROJECT NUMBER: STP F 029-K(2)C/1
 FILE NAME: z10b1940TY02.dgn
 PROJECT LEADER: DMB
 DESIGNED BY: JWS
 QUANTITY SHEET - 2
 PLOT DATE: 11-APR-2012
 DRAWN BY: MAL
 CHECKED BY: DMB
 SHEET 9 OF 123

