

# QUANTITY SHEET 4

STATE OF VERMONT  
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
				ROADWAY	TRAINING	EROSION CONTROL	UTILITIES BID ITEMS	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				75				3280		3355		SM	GEOTEXTILE UNDER STONE FILL	649.31	7			
						555				555		SM	GEOTEXTILE FOR SILT FENCE	649.51	-			
						230				230		SM	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	2.8			
						290				290		SM	GEOTEXTILE FOR FILTER CURTAIN	649.61	2.5			
						195				195		KG	SEED	651.15	0.4			
						63				63		KG	SEED, WINTER RYE	651.17	0.6			
						1250				1250		KG	FERTILIZER	651.18	39.5			
						10				10		T	AGRICULTURAL LIMESTONE	651.20	0.3			
						14				14		T	HAY MULCH	651.25	0.1			
						1100				1100		CM	TOPSOIL	651.35	19.2			
								1300		1300		SM	GRUBBING MATERIAL	651.40	79			
						1				1		LS	EPSC PLAN	652.10	-			
						675				675		HR	MONITORING EPSC PLAN	652.20	4			
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
						9450				9450		SM	TEMPORARY EROSION MATTING	653.20	14.1			
						49				49		CM	TEMPORARY STONE CHECK DAM, TYPE I	653.25	0.3			
						26				26		CM	VEHICLE TRACKING PAD	653.35	0.8			
						7				7		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
						420				420		M	BARRIER FENCE	653.50	2.5			
						1250				1250		M	PROJECT DEMARCATION FENCE	653.55	48.7			
				1						1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
				280						280		CM	SPECIAL PROVISION (CLAY BORROW)	900.608	9.6			
				10						10		CM	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608	0.5			
								564		564		CM	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS AA LOW CEMENT)	900.608	1			
								265730		265730		KG	SPECIAL PROVISION (HIGH PERFORMANCE STEEL, GRADE HPS 485W)	900.635	4			
								2525		2525		KG	SPECIAL PROVISION (STAINLESS STEEL REINFORCING)	900.635	-			
				1						1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, BRIDGE)	900.645	-			
				1						1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650	-			
				1						1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-			
				140						140		SM	SPECIAL PROVISION (MECHANICALLY STABILIZED EARTH RETAINING WALL, RECON)	900.675	-			
				26				200		226		T	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	-			

PROJECT NAME: MORRISTOWN  
 PROJECT NUMBER: STP F 029-K(2)C/1  
 FILE NAME: z10b1940TY04.dgn  
 PROJECT LEADER: DMB  
 DESIGNED BY: JWS  
 QUANTITY SHEET - 4  
 PLOT DATE: 11-APR-2012  
 DRAWN BY: MAL  
 CHECKED BY: DMB  
 SHEET 11 OF 123

