STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS • SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN • SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 182+13 RT CHARLOTTE	TRUCK LANE 500 FT	1	42	42	12.25						2					14'-10" X 15'-5"		X															DI7-2	SHSM		
STA. 183+75 RT CHARLOTTE	NORTH	1	24	12	2.00						1					X 15'-6"		X															M3-1 BLACK ON WHITE	SHSM		
	7	1	24	24	4.00																												MI-4	SHSM		
STA. 183+96 LT CHARLOTTE	ONLY	1	36	30	7.50						2					15'-0" X 15'-6"		X															VR-922R			E-145A
STA. 184+75 RT CHARLOTTE	Shelburne 5	1	72	12	6.00						2					14'-0" X 15'-6"		X															VD2-1		94	
	Burlington 12	1	72	12	6.00																												VD2-1		94	
STA. 186+17 LT CHARLOTTE	SOUTH	1	24	12	2.00						1					16'-6" X		X															M3-3 BLACK ON WHITE	SHSM		
	7	1	24	24	4.00																												MI-4	SHSM		
	↑	1	21	15	2.19																												M6-3 BLACK ON WHITE	SHSM		
												LF	LF	LF	LF -	LF ~~120~~ 122.3	LF -		EA.	LB	LB	LB		LB	LB	LB	LB									
											TOTALS	SF 45.94	SF	EA. -	SF			LF		LF ~~120~~ 122.3			LB			EA.	LB				EA.	EA.	LB			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 6

PROJECT NAME: CHARLOTTE - SOUTH BURLINGTON
PROJECT NUMBER: NH 2907(1)

FILE NAME: p10B206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: p10B206_63.1

PLOT DATE: 4/19/12
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 63 OF 107