STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REFLECTORIZED SIGN	REMARKS • SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN •SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
STA. 262+25 LT CHARLOTTE	Ferrisburg 9	1	72	12	6.00																		X	12 X 13									VDI-1A		94	
	Middlebury 25	1	72	12	6.00																												VDI-1A		94	
	E. Charlotte 3	1	72	12	6.00																												VDI-1A		94	
	Hinesburg 7	1	72	12	6.00																												VDI-1A		94	
STA. 264+00 RT CHARLOTTE	SPEED LIMIT 50	1	24	30	5.00						1					X 14'-5"		X															R2-1	SHSM		
	0070 0404 0500	1	6	10	0.42																												VD-700 MOUNT MILEMARKER PLAQUE BENEATH SPEED LIMIT 50 SIGN			E-138
STA. 265+65 RT CHARLOTTE		1	~~36~~	~~36~~	~~9.00~~		1				2					15'-0" 15'-7" X		X															W4-2R	SHSM		
STA. 274+56 RT CHARLOTTE	0070 0404 0520	1	6	10	0.42						1				8'-2" X			X															VD-700			E-138
												LF	LF	LF	LF ~~8~~ 8.2	LF 45	LF -		EA.	LB	LB	LB		LB ~~304~~ 190	LB	LB	LB								
		TOTALS	SF 38.84	SF 29.84	EA. 1 -	SF						LF			LF 53.2 ~~53~~					LB			EA. 2	LB 190 ~~304~~				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 13

PROJECT NAME: CHARLOTTE - SOUTH BURLINGTON
PROJECT NUMBER: NH 2907(1)

FILE NAME: p10B206.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: p10B206_70.1

PLOT DATE: 4/19/12
DRAWN BY: BMB
CHECKED BY: EPD
SHEET 70 OF 107