

QUANTITY SHEET 5

STATE OF VERMONT
AGENCY OF TRANSPORTATION

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|--|-----------------|--------|----------|---------|-------------|-------|--------------|---------------------------------------|-------------|-------|--------------------------------|------|---------------------------------|
| | | FULL C.E. ITEMS | BRIDGE | TRAINING | ROADWAY | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | 425 | 425 | | LB | SEED | 65I.5 | 21.5 | | | SEED |
| | | | | | 7050 | 7050 | | LB | FERTILIZER | 65I.18 | EST. | 45.0 | LB | DITCH CLEANING |
| | | | | | 30 | 30 | | TON | AGRICULTURAL LIMESTONE | 65I.20 | EST. | 93.4 | LB | SIDE SLOPE TREATMENTS |
| | | | | | 30 | 30 | | TON | HAY MULCH | 65I.25 | EST. | 260 | LB | AREAS OF NARROWING |
| | | | | | 1250 | 1250 | | CY | TOPSOIL | 65I.35 | 80.0 | 5.1 | LB | LEDGE CUT |
| | | | | | 2600 | 2600 | | SY | GRUBBING MATERIAL (6") | 65I.40 | 159.8 | 21.5 | LB | ROUNDING |
| | | | | | 7600 | 7600 | | SY | GRUBBING MATERIAL (2") | 65I.40 | 59.0 | 425 | LB | TOTAL |
| | | | | | 9000 | 9000 | | SY | TEMPORARY EROSION MATTING | 653.20 | 150.4 | | | TOPSOIL |
| | | | | | 5000 | 5000 | | LF | EROSION LOG | 653.60 | 650.0 | 874.2 | CY | SIDE SLOPE TREATMENTS |
| | | | | | 787 | 787 | | SF | TRAFFIC SIGNS, TYPE A | 675.20 | 0.71 | 10.2 | CY | ELECTRICAL CONDUIT INSTALLATION |
| | | | | | 1575 | 1575 | | LB | TUBULAR STEEL SIGN POST | 675.33 | 26.0 | 250 | CY | GUARDRAIL END SECTIONS |
| | | | | | 2350 | 2350 | | LF | SQUARE TUBE SIGN POST AND ANCHOR | 675.34I | 54.0 | 35.6 | CY | LEDGE CUT |
| | | | | | 18 | 18 | | EACH | FOUNDATION FOR TUBULAR STEEL POST | 675.43 | - | 80 | CY | ROUNDING |
| | | | | | 190 | 190 | | EACH | REMOVING SIGNS | 675.50 | - | 1250 | SY | GUARDRAIL END SECTIONS |
| | | | | | 11 | 11 | | EACH | ERECTING SALVAGED SIGNS | 675.60 | - | 150.4 | SY | ROUNDING |
| | | | | | 61 | 61 | | EACH | DELINEATOR WITH STEEL POST | 676.10 | - | 9000 | SY | TOTAL |
| | | | | | 23 | 23 | | EACH | REMOVAL OF EXISTING DELINEATOR | 676.12 | - | | | TEMPORARY EROSION MATTING |
| | | | | | 415 | 415 | | LF | WIRED CONDUIT (2") (PVC) | 678.23 | EST. | 2683 | SY | DITCH CLEANING |
| | | | | | 3 | 3 | | EACH | PULL BOX, STANDARD | 678.25 | - | 4916.6 | SY | SIDE SLOPE TREATMENTS |
| | | | | | 3 | 3 | | EACH | LIGHT POLE BASE | 679.21 | - | 1250 | SY | GUARDRAIL END SECTIONS |
| | | | | | 3 | 3 | | EACH | BREAKAWAY FEATURE FOR LIGHT POLE | 679.23 | - | 150.4 | SY | ROUNDING |
| | | | | | 3 | 3 | | EACH | LIGHT POLE | 679.45 | - | | | TEMPORARY EROSION MATTING |
| | | | | | 3 | 3 | | EACH | BRACKET ARM | 679.47 | - | 2683 | SY | DITCH CLEANING |
| | | | | | 3 | 3 | | EACH | POWER DROP STANCHION, STREET LIGHTING | 679.55 | - | 4916.6 | SY | SIDE SLOPE TREATMENTS |
| | | | | | 1 | 1 | | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | - | 1250 | SY | GUARDRAIL END SECTIONS |
| | | | | | 31 | 31 | | EACH | SPECIAL PROVISION (CORING CONCRETE) | 900.620 | - | 150.4 | SY | ROUNDING |

FILE NAME : V:\P\c\agenc\ANY\K2\22425\CA001\MSTN\10b214_quant_05.dgn
DATE/TIME : 3/17/2014
USER : 4916

| | |
|---------------------------------|----------------------------------|
| QUANTITY SHEET #5 | PROJECT NAME: STOCKBRIDGE-BETHEL |
| | PROJECT NUMBER: STP 2910(I) |
| FILE NAME: z10b214_quant_05.dgn | PLOT DATE: 3/17/2014 |
| PROJECT LEADER: D.E.G. | DRAWN BY: W.G.P. |
| DESIGNED BY: L.M.B. | CHECKED BY: J.P.S. |
| IPARM FILE: z10b214quan5.1 | SHEET 12 OF 397 |