

QUANTITY SHEET 6

**STATE OF VERMONT
AGENCY OF TRANSPORTATION**

SUMMARY OF ESTIMATED QUANTITIES						TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		FULL C.E. ITEMS	BRIDGE	TRAINING	ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					8	8		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-			
					1	1		EACH	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-			SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)
					3	3		EACH	SPECIAL PROVISION (LUMINAIRE, LED)	900.620	-	178,881	SY	MAINLINE
					14,252.5	14,252.5		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	EST.	1313	SY	VT ROUTE 100
					1	1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-	306	SY	ROUNDING
					1	1		LS	SPECIAL PROVISION (INTELLIGENT COMPACTION FOR BITUMINOUS CONCRETE)	900.645	-	180,500	SY	TOTAL
					1	1		LS	SPECIAL PROVISION (INTELLIGENT COMPACTION FOR SUBBASE/RSB)	900.645	-			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)
					1	1		LS	SPECIAL PROVISION (THERMAL PROFILING EQUIPMENT FOR BITUMINOUS MATERIAL)	900.645	-	14,367	TON	WEARING COURSE (TYPE IVS)
					180,500	180,500		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	306.0	28,216	TON	INTERMEDIATE COURSE (TYPE IIS)
					2000	2000		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	21.0	427	TON	SIDE ROADS - WEARING (TYPE IVS)
					179,500	179,500		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	324.0	716	TON	SIDE ROADS - INTERMEDIATE (TYPE IIS)
					27,075	27,075		TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	EST.	150	TON	VT ROUTE 100 - WEARING (TYPE IVS)
					44,500	44,500		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	258.0	301	TON	VT ROUTE 100 - INTERMEDIATE (TYPE IIS)
					25,500	25,500		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	473.0	65	TON	PULLOUTS AND PARKING (TYPE IVS)
					3350	3350		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	165.0	258	TON	ROUNDING
					300	300		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	50.0	44,500	TON	TOTAL
					15,200	15,200		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT, COLD MIX WITH CEMENT)	900.683	184.0			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)
					1500	1500		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-IH OR CRS-IH)	900.683	17.0	25,027	TON	COLD MIXED RECYCLED BITUMINOUS PAVEMENT
					2350	2350		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	96.0	473	TON	ROUNDING
												25,500	TON	TOTAL

QUANTITY SHEET #6

PROJECT NAME: STOCKBRIDGE-BETHEL	PLOT DATE: 3/26/2014
PROJECT NUMBER: STP 2910(I)	DRAWN BY: W.G.P.
FILE NAME: z10b214-quant_06.dgn	DESIGNED BY: L.M.B.
DESIGNED BY: L.M.B.	CHECKED BY: J.P.S.
IPARM FILE: z10b214quant6.i	SHEET 13 OF 397

FILE NAME = W:\Projects\2014\22426\CA001\MSTN\z10b214-quant_06.dgn
DATE/TIME = 3/26/2014 11:39:39
USER =