# ITEM DETAIL SUMMARY SHEET #4

| LOCATION | | | GUARDRAIL | | | | | | | | | | CURB | | | MISCELLANEOUS | | | | | | | | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 621.20 | 621.205 | 621.21 | 621.216 | 621.217 | 621.60 | 621.70 | 621.71 | 621.75 | 621.80 | 616.20 | 616.21 | 616.305 | 301.28 | 604.412 | 604.415 | 604.418 (40) | 613.10 | 649.51 | 651.15 | 651.40 | 653.20 | 653.60 | 676.10 | |
| BEGIN STATION | END STATION | POS. | S.B. GR, GALV. | S.B. GR, GALV. W/ 8 FT POSTS | HD S.B. GR, GALV. | HD S.B. GR, GALV., NESTED | HD S.B. GR, GALV./ NESTED W/ 8 FT POSTS | ANCR. FOR S.B. RAIL | GR APP. SECTION, GALV. TYPE I | GR APP. SECTION, GALV. TYPE II | REMOVE & RESET GR | REMOVAL & DISP. OF GR | GRAN. SLOPE EDGING | VERT GRAN CURB | BITUM. CONC. CURB, TYPE A | SUB. OF C.G., F.G. | REHAB. DI'S CB'S OR MH'S | | CHANGE ELEV OF DI | STONE FILL, TYPE I | GEOTEX FOR SILT FENCE | SEED | GRUB. MAT. (6") | TEMP. EROSION MATTING | EROSION LOG | DEL W/ ST. POST | |
| | | | LF | LF | LF | LF | LF | EA | EA | EA | LF | LF | LF | LF | LF | TON | EA | EA | EA | CY | SY | LB | SY | SY | LF | EA | |
| STOCKBRIDGE: | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 321+50.0 | 327+50.0 | LT | | | | | | | | | | | | | | 17.4 | | | | ~~33.4~~ | | 3.8 | 80.9 | 220.9 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 323+50.0 | 324+50.0 | RT | | | | | | | | | | | | | | 1.2 | | | | | | 1.1 | | 66.6 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 329+00.0 | 330+50.0 | LT | | | | | | | | | | | | | | 4.8 | | | | | | 0.6 | | 38.0 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 329+50.0 | 330+00.0 | RT | | | | | | | | | | | | | | | | | | 10.03<br>~~6.4~~ | | 0.2 | 14.4 | 14.4 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 337+34.0 | 337+34.0 | | | 156.0 | | | | | | | | 125.0 | | | | | | | | | | | | | | | |
| ~~336+81.5~~ | ~~338+35.5~~ | RT | | ~~129.0~~ | | | ~~25.0~~ | 2 | | | | ~~84.0~~ | | | | | | | | | | | | 50.0 | | 2 | SEE VTRANS STANDARD SHEET G-ID. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | PROVIDE ANCHORS AT STA 336+88.0 AND STA 338+29.0. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | SEE SHEET 391 FOR NESTED GUARDRAIL SYSTEM DETAILS. |
| 337+34.0 | | | | 325.0 | | | | | | | 949.5 | 737.5 | | | | | | | | | | | | | | | |
| ~~337+31.5~~ | 353+84.48 | LT | 193.5 | ~~431.0~~ | | | ~~25.0~~ | 3 | | | ~~1095.98~~ | ~~542.0~~ | | | | 11.6 | | | | | | 3.8 | | 221.1 | | 3 | SEE VTRANS STANDARD SHEET G-ID. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | PROVIDE ANCHORS AT STA 337+38.0, STA 339+04.0, AND |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | STA 340+05.5. STEEL BEAM GUARDRAIL CONTINUES INTO BETHEL. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | SEE SHEET 391 FOR NESTED GUARDRAIL SYSTEM DETAILS. |
| BETHEL: | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | 11 | | 6 | | | | | | | | |
| B 0+00.0 | B 170+28.0 | LT/RT | | | | | | | | | | | | | | | ~~9~~ | ~~1~~ | ~~1~~ | | ~~178.0~~ | | | | ~~1750.0~~ | | SHALL BE PERFORMED AS DIRECTED BY THE ENGINEER. |
| | | | | | | | | | | | 1050.0 | | | | | | | | | | | | | | | | |
| B 0+00.0 | B 11+13.0 | LT | 64.5 | | | | | 1 | | | ~~1113.0~~ | | | | | | | | | ~~14.3~~ | | 0.9 | 34.7 | 50.2 | | 1 | STEEL BEAM GUARDRAIL IS A CONTINUATION FROM STOCKBRIDGE. |
| 17+46.0 | 18+71.0 | RT | | 125.0 | | | | 2 | | | | | | | | | | | | | | | | | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 17+43.0 | 36+94.0 | | | 506.0 | | | | | | | 1350.0 | 350.0 | | | | | | | | | | | | | | | |
| B ~~16+98.0~~ | B ~~37+02.0~~ | LT | 114.5 | ~~616.5~~ | | | | 2 | | | ~~1387.5~~ | ~~342.5~~ | | | | 3.6 | | | | ~~77.8~~ | 92.06 | 6.8 | 185.5 | 399.7 | | 2 | SEE VTRANS STANDARD SHEET G-ID. |
| 18+10.0 | 18+34.0 | RT | | | | | | | | | | | | | | | | | | 16.49 | | | | | | | PROVIDE ANCHORS AT STA B 17+04.5 AND STA B 36+95.5. |
| 18+18.0 | 18+28.0 | LT | | | | | | | | | | | | | | | | | | 5.48 | | | | | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| B ~~22+50.0~~ | B 29+50.0 | RT | | | | | | | | | | | | | | | | | | ~~45.0~~ | | 2.0 | 119.4 | 119.4 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| 41+60.0 | 42+03.0 | RT | | 1427.0 | | | | | | | | 1637.5 | | | | | | | | 5.57 | | | | | | | |
| B 41+89.0 | B 58+17.0 | LT | 127.0 | ~~1479.0~~ | | | | 2 | | | | ~~1628.0~~ | | | | 6.0 | | | | ~~191.3~~ | 734.12 | 11.2 | 495.6 | 659.1 | | 2 | SEE VTRANS STANDARD SHEET G-ID. |
| 44+00.0 | 44+35.0 | RT | | | | | | | | | | | | | | | | | | 15.55 | | | | | | | PROVIDE ANCHORS AT STA B 42+29.5 AND STA B 56+95.5. |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| B 46+00.0 | B 46+50.0 | RT | | | | | | | | | | | | | | | | | | 4.74 | | 0.4 | | 25.6 | | | SEE SHEET 25 FOR SIDE SLOPE TREATMENT DETAILS. |
| | | | | | | | | | | | | 612.5 | | | | | | | | | | | | | | | |
| B 61+56.0 | B 67+60.0 | LT | | | | | | | | | | ~~604.0~~ | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 862.5 | | | | | | | | | | | | | | | |
| B 74+93.0 | B 83+53.0 | LT | | | | | | | | | | ~~860.0~~ | | | | | | | | 3.11 | | | | | | | |
| THIS SHEET SUBTOTALS: | | | - | 2655.5 | - | - | 50.0 | 9 | - | - | 3596.48 | 4060.5 | - | - | - | 44.6 | 9 | 1 | 1 | ~~368.2~~<br>887.15 | 178.0 | 30.8 | 930.5 | 1865.0 | 1750.0 | 10 | |
| | | | | | | | | 12 | | | | | | | | | | | | | | | | | | | |

| | |
|---|---|
| ITEM DETAIL SUMMARY SHEET #4 | PROJECT NAME: STOCKBRIDGE-BETHEL<br>PROJECT NUMBER: STP 2910(1) |
| | FILE NAME: z10b214_1ds_04.dgn<br>PROJECT LEADER: D.E.G.<br>DESIGNED BY: L.M.B.<br>IPARM FILE: z10b2141ds4.1 |
| | PLOT DATE: 3/17/2014<br>DRAWN BY: W.G.P.<br>CHECKED BY: J.P.S.<br>SHEET 17 OF 397 |

FILE NAME = V:\Projects\ANYWK2\22426\CADD_MSTN\z10b214_1ds_04.dgn
DATE/TIME = 3/17/2014
USER = 4916